



Florida Department of Transportation

CHARLIE CRIST
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

STEPHANIE KOPELOUSOS
SECRETARY

December 21, 2007

Dr. Leslie McCarthy, PhD, P.E.
Program Operations Engineer
Federal Highway Administration
545 John Knox Road, Suite 200
Tallahassee, Florida 32303

Re: Office of Design, Specifications
Section 785
Proposed Specification: 7850531 – Intelligent Transportation Systems-Infrastructure

Dear Dr. McCarthy:

We are submitting, for your approval, two copies of a proposed Supplemental Specification for Intelligent Transportation Systems-Infrastructure.

This change was proposed by Tom Malerk of the State Materials Office to specify that precast products to be obtained from plants listed on Producers with Accepted Quality Control Programs.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via Email to SP965DB or duane.brautigam@dot.state.fl.us.

If you have any questions relating to this specification change, please call Duane F. Brautigam, State Specifications Engineer at 414-4110.

Sincerely,

Signature on file

Duane F. Brautigam, P.E.
State Specifications Engineer

DFB/sh

Attachment

cc: Gregory Jones, General Counsel
Florida Transportation Builders' Assoc.
State Construction Engineer

785—INTELLIGENT TRANSPORTATION SYSTEMS—INFRASTRUCTURE.
(REV ~~12-7-06~~11-17-07*11-9-07*~~)(FA 1-28-07)(7-07)~~

SUBARTICLE 785-5.3.1 (of the Supplemental Specifications) is deleted and the following substituted:

785-5.3 Installation Requirements.

785-5.3.1 General: Provide a drawing that depicts the details of the proposed equipment shelter installation, including site layout, fencing, and all other features. Submit this drawing to the Engineer for approval prior to the start of construction.

Furnish concrete in accordance with Section 346. Perform all concrete work in accordance with Section 400. *Obtain precast products from a plant that is currently on the list of Producers with Accepted Quality Control Programs for Incidental Precast products. Producers seeking inclusion on the list shall meet the requirements of 105-3.*

Contact local building officials for permit applications and submit them to the Engineer for approval and execution. The Contractor shall be responsible for obtaining all permits and their associated applications, filling out the applications, obtaining a Department signature, and then submitting the permit application to the regulating agency.

INTELLIGENT TRANSPORTATION SYSTEMS–INFRASTRUCTURE.**(REV 11-9-07)**

SUBARTICLE 785-5.3.1 (of the Supplemental Specifications) is deleted and the following substituted:

785-5.3 Installation Requirements.

785-5.3.1 General: Provide a drawing that depicts the details of the proposed equipment shelter installation, including site layout, fencing, and all other features. Submit this drawing to the Engineer for approval prior to the start of construction.

Furnish concrete in accordance with Section 346. Perform all concrete work in accordance with Section 400. Obtain precast products from a plant that is currently on the list of Producers with Accepted Quality Control Programs. Producers seeking inclusion on the list shall meet the requirements of 105-3.

Contact local building officials for permit applications and submit them to the Engineer for approval and execution. The Contractor shall be responsible for obtaining all permits and their associated applications, filling out the applications, obtaining a Department signature, and then submitting the permit application to the regulating agency.