

EXPECTED IMPLEMENTATION JULY 2008

355 THRESHOLD VALUES AND REMEDIAL WORK. (REV 2-8-08) (FA 2-19-08) (7-08)

SUBARTICLE 355-4.3 (of the Supplemental Specifications). Table 355-1 is deleted and the following substituted:

355-4.3 Threshold Values and Remedial Work: Threshold values and associated remedial work for the Concrete Pavement are specified in Table 355-1.

DEFICIENCY TYPE	THRESHOLD LEVEL	REMEDIAL ACTION
Rideability	Ride Number < 3.70	Grind all deficient sections in accordance with Section 352.
Spalling in the wheel path	Four areas in any Lane Mile exceeding 1 inch in width and exceeding 6 inches in length OR any single area exceeding 3 inches in width.	Full depth slab replacement for a minimum of 6 feet in length and the full width of the slab in accordance with Section 353.
Spalling outside the wheel path	Four areas in any Lane Mile exceeding 1 1/2 inches in width and 12 inches in length OR any single area exceeding 3 inches in width and 12 inches in length.	Full depth slab replacement for a minimum of 6 feet in length and the full width of the slab in accordance with Section 353.
Cracking	Four Cracks in any Lane Mile with width exceeding 1/8 inch OR any Crack exceeding 3/16 inch.	Full depth slab replacement for a minimum of 6 feet in length and the full width of the slab in accordance with Section 353.
Shattered Slab	Cracking patterns that divide the slab into three or more segments	Full slab replacement in accordance with Section 353.