

EXPECTED IMPLEMENTATION JULY 2008

400 CONCRETE STRUCTURES. (REV 12-6-07) (FA 1-7-08) (7-08)

SUBARTICLE 400-17.4 (Page 388) is deleted and the following substituted:

400-17.4 Alternate Procedure: As an alternate procedure, in lieu of the time delay periods set forth in 400-17.1 and 400-17.3, test beams or cylinders may be cast from representative concrete and cured identically with the concrete in the corresponding structural component. Make the test beams in accordance with ASTM C 31 and test them in accordance with ASTM C 78. When the test results indicate a minimum flexural strength of 550 psi or indicate a minimum required compressive strength, concrete bridge decks and culverts may be opened to traffic or the superstructure and beams may be placed on caps.

D

R

A

F

T