

EXPECTED IMPLEMENTATION JULY 2008

700 HIGHWAY SIGNAGE. (REV 11-9-07) (FA 12-19-07) (7-08)

SUBARTICLE 700-7.2 (of the Supplemental Specifications) is deleted and the following substituted:

700-7.2 Mixing and Placing Concrete: For batching and mixing of concrete for footings, meet the requirements of Section 346, except that the Engineer will allow hand mixing by approved methods where the quantity to be mixed does not exceed 1/2 yd³. Use cast-in-place or precast concrete for the footings. Obtain precast concrete footings from a plant that is currently on the list of Producers with Accepted Quality Control Programs. Producers seeking inclusion on the list shall meet the requirements of 105-3.

D

R

A

F

T