

EXPECTED IMPLEMENTATION JULY 2008

D

715 FOUNDATIONS FOR LIGHT POLES – CONCRETE FOUNDATIONS. (REV 10-13-07) (FA 12-19-07) (7-08)

SUBARTICLE 715-6.1 (of the Supplemental Specifications) is deleted and the following substituted:

715-6.1 Concrete Foundations: Provide foundations for light poles of the sizes and shapes shown in the plans. Construct precast or cast-in-place concrete foundations in accordance with the Design Standards. Obtain precast foundations from a plant that is currently on the Department's list of Producers with Accepted Quality Control Programs. Producers seeking inclusion on the list shall meet the requirements of 105-3.

R

A

F

T