

EXPECTED IMPLEMENTATION JULY 2008

785 INTELLIGENT TRANSPORTATION SYSTEMS–INFRASTRUCTURE. (REV 11-9-07) (FA 1-10-08) (7-08)

SUBARTLICLE 785-5.3.1 (of the Supplemental Specifications) is deleted and the following substituted:

785-5.3 Installation Requirements.

785-5.3.1 General: Provide a drawing that depicts the details of the proposed equipment shelter installation, including site layout, fencing, and all other features. Submit this drawing to the Engineer for approval prior to the start of construction.

Furnish concrete in accordance with Section 346. Perform all concrete work in accordance with Section 400. Obtain precast products from a plant that is currently on the list of Producers with Accepted Quality Control Programs. Producers seeking inclusion on the list shall meet the requirements of 105-3.

Contact local building officials for permit applications and submit them to the Engineer for approval and execution. The Contractor shall be responsible for obtaining all permits and their associated applications, filling out the applications, obtaining a Department signature, and then submitting the permit application to the regulating agency.

D

R

A

F

T