

PORTLAND CEMENT CONCRETE.

(REV 10-15-07) (7-08)

ARTICLE 346-1 (of the Supplemental Specifications) is deleted and the following substituted:

346-1 Description.

Use concrete composed of a mixture of portland cement, aggregate, water, and, where specified, admixtures, pozzolan and ground granulated blast furnace slag. Deliver the portland cement concrete to the site of placement in a freshly mixed, unhardened state.

Obtain concrete from a plant that is currently on the list of Producers with accepted Quality Control Program. Producers seeking inclusion on the list shall meet the requirements of 105-3. If the concrete production facility's Quality Control Plan is suspended, the Contractor is solely responsible to obtain the services of another concrete production facility with an approved Quality Control Program or await the re-approval of the affected concrete production facility's Quality Control Plan prior to the placement of any further concrete on the project. There will be no changes in the contract time or completion dates. Bear all delay costs and other costs associated with the concrete production facility approval or re-approval.

SUBARTICLE 346-2.5.3.3 (of the Supplemental Specifications) is deleted and the following substituted:

346-2.5.3.3 Self Consolidating Concrete Admixtures for Precast/Prestressed Concrete: Use self consolidating concrete meeting the requirements of 105-3 and this Section.