

EXPECTED IMPLEMENTATION JANUARY 2009

929 POZZOLANS AND SLAG – APPROVED LABORATORY. **(REV 6-23-08) (FA 7-24-08) (1-09)**

SUBARTICLE 929-1.2 (of the Supplemental Specifications) is deleted and the following substituted:

929-1.2 Approved Laboratory: The cementitious materials supplier's testing laboratory must maintain Cement and Concrete Reference Laboratory (CCRL) accreditation, be currently inspected by the CCRL, be actively participating in the CCRL proficiency program and have all deficiencies noted at the time of inspection corrected. The laboratory must authorize the CCRL to send a copy of the final inspection report to the State Materials Office.

D

R

A

F

T