

EXPECTED IMPLEMENTATION JULY 2009

715 FOUNDATIONS FOR LIGHT POLES – INSTALLATION. (REV 1-16-09) (FA 1-26-09) (7-09)

SUBARTICLE 715-6.3 (of the Supplemental Specifications) is deleted and the following substituted:

715-6.3 Installation: Do not erect roadway light poles or high mast light poles until the concrete strength in the cast-in-place foundation is at least 2,500 psi. Determine concrete strength from tests on a minimum of two test cylinders sampled and tested in accordance with ASTM C 31 and ASTM C 39 and verifying test results have been provided to the Engineer.

Fill the voids around precast concrete foundations under roadway light poles with flowable fill meeting the requirements of Section 121 or clean sands placed using hydraulic methods to a level 6 inches below grade.

D

R

A

F

T