

EXPECTED IMPLEMENTATION JULY 2009

D

INSTALLATIONS REQUIREMENTS – BASE MOUNTED (TYPE IV AND V) AND PEDESTAL MOUNTED (TYPE III) TRAFFIC MONITORING SITE CABINETS. (REV 5-6-08) (FA 10-14-08) (7-09)

SUBARTICLE 746-3.3 (of the Special Provisions) is deleted and the following substituted:

746-3.3 Base Mounted (Type IV and V) and Pedestal Mounted (Type III) Traffic Monitoring Site Cabinets: Construct the base for the cabinet with concrete meeting the requirements of Section 347 and finish the surface smooth and level.

Temporarily seal the ends of the conduit risers located in the base before placing concrete. Ensure that the end of the conduit riser(s) is a minimum of 2 inches above the finished surface of the concrete base.

Use anchor bolts to fasten base mounted cabinet to the concrete base. Seal the joint between the bottom of the cabinet and the concrete base (inside and outside of cabinet) with a clear silicone rubber sealant.

R

A

F

T