



## Florida Department of Transportation

**CHARLIE CRIST**  
GOVERNOR

605 Suwannee Street  
Tallahassee, FL 32399-0450

**STEPHANIE KOPELOUSOS**  
SECRETARY

April 9, 2009

Monica Gourdine  
Program Operations Engineer  
Federal Highway Administration  
545 John Knox Road, Suite 200  
Tallahassee, Florida 32303

Re: Office of Design, Specifications  
Section 008  
Proposed Specification: 0080301 - Prosecution and Progress

Dear Ms. Gourdine:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

These changes were proposed by David Sadler of the State Construction Office, to define the responsibility of the Contractor and to be in conformance with the rest of the specification language.

Please review and transmit your comments, if any, within four weeks. Comments should be sent via Email to ST986RP or rudy.powell@dot.state.fl.us.

If you have any questions relating to this specification change, please call Rudy Powell, State Specifications Engineer at 414-4110.

Sincerely,

Rudy Powell, Jr., P.E.  
State Specifications Engineer

RP/sh

Attachment

cc: Gregory Jones, Chief Civil Litigation  
Florida Transportation Builders' Assoc.  
State Construction Engineer

**008—PROSECUTION AND PROGRESS.**

——(REV ~~5-31-07~~~~2-16-09~~)-(FA ~~10-17-07~~)-(7-08)

SUBARTICLE 8-3.1 (Page 79) is deleted and the following substituted:

**8-3.1 Compliance with Time Requirements:** Commence work in accordance with the ~~approved~~*accepted* working schedule and provide sufficient labor, materials and equipment to complete the work within the time limit(s) set forth in the proposal. Should the Contractor fail to furnish sufficient and suitable equipment, forces, and materials, as necessary to prosecute the work in accordance with the required schedule, the Engineer may withhold all estimates that are, or may become due, or suspend the work until the Contractor corrects such deficiencies.

SUBARTICLE 8-4.1 (of the Supplemental Specifications) is deleted and the following substituted:

**8-4.1 Night Work:** During active nighttime operations, furnish, place and maintain lighting sufficient to permit proper workmanship and inspection. Use lighting with 5 ft-cd minimum intensity. Arrange the lighting to prevent interference with traffic or produce undue glare to property owners. Operate such lighting only during active nighttime construction activities. Provide a light meter to demonstrate that the minimum light intensity is being maintained.

Lighting may be accomplished by the use of portable floodlights, standard equipment lights, existing street lights, temporary street lights, or other lighting methods approved by the Engineer.

Submit a lighting plan at the Preconstruction Conference for review and ~~approval~~*acceptance* by the Engineer. Submit the plan on standard size plan sheets (not larger than 24 by 36 inch), and on a scale of either 100 or 50 feet to 1 inch. Do not start night work prior to the Engineer's ~~approval~~*acceptance* of the lighting plan.

During active nighttime operations, furnish, place and maintain variable message signs to alert approaching motorists of lighted construction zones ahead. Operate the variable message signs only during active construction activities.

Include compensation for lighting for night work in the Contract prices for the various items of the Contract. Take ownership of all lighting equipment for night work.

**PROSECUTION AND PROGRESS.**  
**(REV 2-16-09)**

SUBARTICLE 8-3.1 (Page 79) is deleted and the following substituted:

**8-3.1 Compliance with Time Requirements:** Commence work in accordance with the accepted working schedule and provide sufficient labor, materials and equipment to complete the work within the time limit(s) set forth in the proposal. Should the Contractor fail to furnish sufficient and suitable equipment, forces, and materials, as necessary to prosecute the work in accordance with the required schedule, the Engineer may withhold all estimates that are, or may become due, or suspend the work until the Contractor corrects such deficiencies.

SUBARTICLE 8-4.1 (of the Supplemental Specifications) is deleted and the following substituted:

**8-4.1 Night Work:** During active nighttime operations, furnish, place and maintain lighting sufficient to permit proper workmanship and inspection. Use lighting with 5 ft-cd minimum intensity. Arrange the lighting to prevent interference with traffic or produce undue glare to property owners. Operate such lighting only during active nighttime construction activities. Provide a light meter to demonstrate that the minimum light intensity is being maintained.

Lighting may be accomplished by the use of portable floodlights, standard equipment lights, existing street lights, temporary street lights, or other lighting methods approved by the Engineer.

Submit a lighting plan at the Preconstruction Conference for review and acceptance by the Engineer. Submit the plan on standard size plan sheets (not larger than 24 by 36 inch), and on a scale of either 100 or 50 feet to 1 inch. Do not start night work prior to the Engineer's acceptance of the lighting plan.

During active nighttime operations, furnish, place and maintain variable message signs to alert approaching motorists of lighted construction zones ahead. Operate the variable message signs only during active construction activities.

Include compensation for lighting for night work in the Contract prices for the various items of the Contract. Take ownership of all lighting equipment for night work.