



Florida Department of Transportation

CHARLIE CRIST
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

STEPHANIE KOPELOUSOS
SECRETARY

April 2, 2009

Monica Gourdine
Program Operations Engineer
Federal Highway Administration
545 John Knox Road, Suite 200
Tallahassee, Florida 32303

Re: Office of Design, Specifications
Section 102
Proposed Specification: 1020905 Barrier Wall (Temporary)

Dear Ms. Gourdine:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

These changes were proposed by Andy Keel of the State Roadway Design Office to clarify the requirements for the approval of different types of temporary barrier wall.

Please review and transmit your comments, if any, within four weeks. Comments should be sent via Email to ST986RP or rudy.powell@dot.state.fl.us.

If you have any questions relating to this specification change, please call Rudy Powell, State Specifications Engineer at 414-4110.

Sincerely,

Rudy Powell, Jr., P.E.
State Specifications Engineer

RP/dt

Attachment

cc: Gregory Jones, Chief Civil Litigation
Florida Transportation Builders' Assoc.
State Construction Engineer

MAINTENANCE OF TRAFFIC.**(REV 02-02-09)**

SUBARTICLE 102-9.5.2 (of the Supplemental Specifications) is deleted and the following substituted:

102-9.5.2 Barrier Wall (Temporary): Furnish, install, maintain, remove and relocate a temporary barrier wall in accordance with the plans. Ensure that temporary concrete barrier wall for use on roadway sections, complies with *Section 521 and* Index No. *412*, 415 or 414 as specified in the plans. Ensure that temporary concrete barrier wall for use on bridge and wall sections, complies with Index No 414 as specified in the plans. Ensure that temporary water filled barrier wall used on roadway sections *meets the NCHRP Report 350 criteria and is* conforms to the requirements of the pre-approved alternatives listed on the *Qualified Products List (QPL)*, unless otherwise called for in the plans. Ensure that proprietary barrier walls for use on roadway sections meet NCHRP Report 350 criteria and be identified on the QPL. Barriers meeting the requirements of Index No. *412*, 415 or temporary water filled barriers on the QPL will not be accepted as an alternate to barriers meeting the requirements of Index No. 414.

MAINTENANCE OF TRAFFIC.**(REV 02-02-09)**

SUBARTICLE 102-9.5.2 (of the Supplemental Specifications) is deleted and the following substituted:

102-9.5.2 Barrier Wall (Temporary): Furnish, install, maintain, remove and relocate a temporary barrier wall in accordance with the plans. Ensure that temporary concrete barrier wall for use on roadway sections, complies with Section 521 and Index No. 412, 415 or 414 as specified in the plans. Ensure that temporary concrete barrier wall for use on bridge and wall sections, complies with Index No 414 as specified in the plans. Ensure that temporary water filled barrier wall used on roadway sections meets the NCHRP Report 350 criteria and is listed on the Qualified Products List (QPL). Barriers meeting the requirements of Index No. 412, 415 or temporary water filled barriers on the QPL will not be accepted as an alternate to barriers meeting the requirements of Index No. 414.