

**125 EXCAVATION FOR STRUCTURES AND PIPE – ACCEPTANCE PROGRAM.
(REV 6-3-09) (FA 8-13-09) (1-10)**

SUBARTICLE 125-9.1 (Page 187) is deleted and the following substituted:

125-9.1 General Requirements: Meet the requirements of 120-10, except replace the requirements of 120-10.1.6 with 125-9.1.1, 120-10.2 with 125-9.2, 120-10.3 with 125-9.3, and 120-10.4 with 125-10.

125-9.1.1 Reduced Testing Frequency: When no Resolution testing is required for 6 consecutive LOTs, or if required, the Quality Control test data was upheld, reduce the Quality Control density testing to one test every two Lots by identifying the substantiating tests in the Density Log Book and notifying the Engineer in writing prior to starting reduced frequency of testing. Generate random numbers based on the two LOTs under consideration. When Quality Control test frequency is reduced to one every two LOTs, obtain the Engineer's approval to place more than one LOT over an untested LOT. Assure similar compaction efforts for the untested sections. If the Verification test fails, and Quality Control test data is not upheld by Resolution testing the Quality Control testing will revert to the original frequency.