

320 PAVING EQUIPMENT.

(REV 7-29-09) (FA 8-11-09) (1-10)

SUBARTICLE 320-5.1.2 (Page 246) is deleted and the following substituted:

320-5.1.2 Automatic Screed Control: For all asphalt courses, placed with mechanical spreading and finishing equipment, equip the paving machine with automatic longitudinal screed controls of either the skid type, traveling stringline type, or non-contact averaging ski type. Ensure that the length of the skid, traveling stringline, or non-contact averaging ski is at least 25 feet. On the final layer of base, overbuild, and structural courses, and for friction courses, use the joint matcher in lieu of the skid, traveling stringline, or non-contact averaging ski on all passes after the initial pass. Furnish a paving machine equipped with electronic cross slope controls.

SUBARTICLE 320-5.3.1 (Page 246) is deleted and the following substituted:

320-5.3.1 Steel-Wheeled Rollers: Provide compaction equipment capable of meeting the density requirements described in these Specifications. In the event that density testing is not required, provide a tandem steel-wheeled roller weighing 5 to 15 tons for seal rolling, and for the final rolling, use a separate roller with a weight of 5 to 15 tons. Variations from these requirements shall be approved by the Engineer.