

715 HIGHWAY LIGHTING SYSTEM.
(REV 8-4-09) (FA 8-11-09) (1-10)

ARTICLE 715-1 (Page 808) is expanded by the following:

715-1 Description.

Install a highway lighting system in accordance with the details shown in the plans. Include in the system the light poles, bases, luminaires, ballasts, pull boxes, cable, conduit, substations, expansion joints, protective devices, transformers and control devices; all as specified or required for the complete facility. Use pole assemblies listed on the Department's Qualified Products List (QPL) when standard aluminum pole assemblies or standard high mast light assemblies are required by the Contract Documents.

Provide metal lighting poles, excluding high mast lighting, with internal vibration damping devices in accordance with Design Standard 17515 in all installations on bridges, walls and concrete median barriers.

ARTICLE 715-16 (Pages 812 and 813) is deleted and the following substituted:

715-16 Method of Measurement.

The quantities to be paid for will be as follows, completed and accepted:

(a) Conduit: The length, in feet, including elbows, sweeps, connecting hardware, trenching and backfill as indicated in the plans and the Design Standards, and the cost of restoring cut pavement, sidewalks, sod, and etc., to its original condition.

(b) Luminaire and Truss Arm: The Contract unit price will include the truss arm, luminaire with lamp, and all necessary mounting hardware as indicated in the plans and the Design Standards.

(c) Load Center: The Contract unit price will include the service pole, insulators, weatherheads, transformers, enclosures, panel boards, breakers, safety switches, H.O.A. switches, lighting protectors, fuses, photo electric assembly, meter base, and all external and internal conduit and conductors for the service as indicated in the plans and the Design Standards.

(d) Light Pole Foundation: The Contract unit price will include the foundation and anchor bolts with lock nuts and washers as indicated in the plans and the Design Standards.

(e) Luminaire: The Contract unit price will include the luminaire with lamp and necessary mounting hardware as indicated in the plans and the Design Standards.

(f) Pull Box: The Contract unit price will include the pull box and cover as indicated in the plans and the Design Standards.

(g) High Mast Parts: The Contract unit price will include the part specified with all mounting hardware as indicated in the Contract Documents and the Design Standards.

(h) Frangible Base for Light Pole: The Contract unit price will include the frangible base, attachments, bolts, and washers as indicated in the plans and the Design Standards.

(i) Photo Electric Control Assembly: The Contract unit price will include the photo electric control, transformers, conduit, and conductors as indicated in the plans and the Design Standards.

(j) Pre-Fab Pilaster: The Contract unit price will include the pilaster and all mounting hardware as indicated in the plans.

(k) High Mast Lighting Pole Complete: The Contract unit price will include the pole, luminaires with lamps, lowering system, breakers and anchor bolts with lock nuts and washers as indicated in the plans and the Design Standards.

(l) Conductor: The length, in feet, as indicated in the plans and the Design Standards.

(m) Lighting Pole Complete: The Contract unit price will include the pole, internal vibration damping device, truss arm, luminaire with lamp, anchor bolts with lock nuts and washers, frangible base and foundation.

(n) Pole Cable Distribution System: The Contract Unit price will include the surge protector, fuse holders with fuses, waterproof connectors and the waterproof wiring connection to the luminaries.