

EXPECTED IMPLEMENTATION JANUARY 2011

D

346 PORTLAND CEMENT CONCRETE.
(REV 4-13-10) (FA 4-15-10) (1-11)

SUBSECTION 346-3.2 (Page 322) the second paragraph is deleted and the following substituted:

Test each load of concrete for slump to ensure the concrete is within the limits of 346-6.4. Ensure that the slump loss is gradual as evidenced by slump loss tests described below. The concrete elapsed time is the sum of the mixing and transit time, the placement time, the time required for removal of any temporary casing that causes or could cause the concrete to flow into the space previously occupied by the temporary casing and bolt/embedment installation.

R

A

F

T