

EXPECTED IMPLEMENTATION JANUARY 2011

D

455 STRUCTURES FOUNDATIONS.
(REV 6-14-10) (FA 7-29-10) (1-11)

SUBARTICLE 455-7.5 (Page 544) is deleted and the following substituted:

455-7.5 Preparation for Transportation: Cut any strands protruding beyond the ends of the pile flush with the surface of the concrete using an abrasive cutting blade before transporting the piles from the casting yard.

Cut and patch the metal lifting devices in accordance with 450-9.2.1.

R

A

F

T