

# EXPECTED IMPLEMENTATION JULY 2011

D

## 650 VEHICULAR SIGNAL ASSEMBLIES. (REV 2-2-11) (FA 2-7-11) (7-11)

ARTICLE 650-2 (Page 60) is deleted and the following substituted:

### 650-2 Materials.

Use signal housings, light emitting diode (LED) modules, backplates, and signal auxiliaries currently listed on the Department's Approved Product List (APL). Ensure that all equipment is marked in accordance with Section 603.

R

SUBARTICLE 650-3.1(Page760) is deleted and the following substituted:

**650-3.1 Preassembly:** Pre-assemble the signal heads when more than one signal section is required prior to installation at the site. Furnish signal heads with LED modules, backplates, and visors. Use tunnel visors unless otherwise specified in the Contract Documents. Install the LED ball module in the door so that the UP arrow or the word UP or TOP is in the up orientation of the signal housing. Install the LED arrow modules in the signal housing door in the direction of the intended use.

A

SUBARTICLE 650-4.2 (Page 761) is deleted and the following substituted:

**650-4.2 Furnish and Install:** The Contract unit price per assembly for Traffic Signal, furnished and installed, will consist of the traffic signal assembly, including all attachment hardware necessary to make a complete unit, all mounting brackets, drop-pipe, disconnect hangers, backplates, visors, LED modules, labor, and materials necessary for a complete and accepted installation.

F

ARTICLE 650-5 (Page 762) is deleted and the following substituted:

### 650-5 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section.  
Payment will be made under:

Item No. 650- 5- Traffic Signal–per assembly.

T