

MOTORIST AID CALL BOX RELOCATION.

(REV 8/24/10) (1/11)

PAGE 807. The following new Section is added after Section 713:

SECTION 714 MOTORIST AID CALL BOX RELOCATION

714-1 Description.

Relocate existing Motorist Aid Call Boxes and construct new Motorist Aid Call Box Concrete Pads in accordance with Index 17600 and the details and notes shown in the Contract Documents.

714-2 Materials.

Use the existing call box assemblies and any additional new materials required to complete the installation.

Use concrete meeting the requirements of Section 346.

Use reinforcing steel meeting the requirements of Section 415.

714-3 Construction of Concrete Pads.

714-3.1 Forms: Provide forms as specified in 520-3.

714-3.2 Foundations: Prepare foundation in accordance with 522-4.

714-3.3 Placing Concrete: Place the concrete as specified in 520-5.

714-3.4 Finishing: Finish concrete as specified in 522-7.

714-3.5 Curing: Cure the concrete as specified in 520-8.

714-4 Relocating Existing Call Box Assemblies.

Schedule relocation as to allow no more than one motorist aid call box per direction of travel within the length of the project to be out of service at any time.

Do not remove motorist aid call box assembly from existing concrete pad except to relocate to new location.

Any damage to the existing call box assembly caused by the Contractor's operations shall be repaired at no additional expense to the Department.

714-5 Method of Measurement.

The quantities to be paid will be the number of motorist aid call box assemblies relocated.

714-6 Basis of Payment.

Price and payment will be full compensation for all materials, equipment and work required to relocate the call boxes including breakaway devices and signs and concrete foundations and pads.

714-6.3 Payment Items: Payment will be made under:

Item No. 714- 1-5- Motorist Aid Call Box (Relocate) – per assembly.

