

ORIGINATION FORM

Date: 5-18-11

Originator: Greg Sholar

Contact Information: SMO (352-955-2920)

Specification Title: Superpave Asphalt Concrete

Specification Section, Article, or Subarticle Number: 334

Why does the existing language need to be changed? 1. The specification requires that asphalt mixture samples be conditioned in a covered, shallow, flat pan prior to testing. This is not in agreement with AASHTO R 30, which does not require covering the pan.

2. There are conflicts with specification references to sections 320 and 330 due to a rewrite of those sections.

Summary of the changes: 1. Delete “covered” from the sentence in subarticle 334-5.1.1.

2. Change the specification reference in articles/subarticles 334-1.4, 334-3.2.7, 334-5.1.2, 334-5.8, and 334-7.

Are these changes applicable to all Department jobs? Yes. If not, what are the restrictions?

Will these changes result in an increase or decrease in project costs? No. If yes, what is the estimated change in costs?

With who have you discussed these changes? SMO Bituminous staff

What other offices will be impacted by these changes? Construction, but not in a negative way.

Are changes needed to the PPM, Design Standards, SDG, CPAM or other manual? No.

Is a Design Bulletin, Construction Memo, or Estimates Bulletin needed? No.

Contact the State Specifications Office for assistance in completing this form.
Rudy Powell 850-414-42820 rudypowell@dot.state.fl.us
Frances Thomas 850-414-4101 frances.thomas@dot.state.fl.us
Debbie Toole 850-414-4114 deborah.toole@dot.state.fl.us
Andy Harper 850-414-4127 clifton.harper@dot.state.fl.us



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

ANANTH PRASAD, P.E.
SECRETARY

M E M O R A N D U M

DATE: June 2, 2011

TO: Specification Review Distribution List

FROM: Rudy Powell, Jr., P.E., State Specifications Engineer

SUBJECT: Proposed Specification: **3340104 Superpave Asphalt Concrete.**

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

This change was proposed by Greg Sholar of the State Materials Office to require that asphalt mixture samples be conditioned in a covered, shallow, flat pan prior to testing.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or to my attention via e-mail at SP965RP or rudy.powell@dot.state.fl.us. Comments received after **June 30, 2011** may not be considered. Your input is encouraged.

RP/cah
Attachment

SUPERPAVE ASPHALT CONCRETE.
(REV 5-19-11)

SUBARTICLE 334-1.4 (of the Supplemental Specification) is deleted and the following substituted:

334-1.4 Thickness: The total thickness of the Type SP asphalt layer(s) will be the plan thickness as shown in the Contract Documents. Before paving, propose a thickness for each individual layer meeting the requirements of this specification, which when combined with other layers (as applicable) will equal the plan thickness. For construction purposes, the plan thickness and individual layer thickness will be converted to spread rate based on the maximum specific gravity of the asphalt mix being used, as well as the minimum density level, as shown in the following equation:

$$\text{Spread rate (lbs/yd}^2\text{)} = t \times G_{\text{mm}} \times 43.3$$

Where: t = Thickness (in.) (Plan thickness or individual layer thickness)

G_{mm} = Maximum specific gravity from the verified mix design

The weight of the mixture shall be determined as provided in 320-~~23~~.2. For target purposes only, spread rate calculations should be rounded to the nearest whole number.

Note: Plan quantities are based on a G_{mm} of 2.540, corresponding to a spread rate of 110 lbs/yd²-in. Pay quantities will be based on the actual maximum specific gravity of the mix being used.

SUBARTICLE 334-3.2.7 (of the Supplemental Specification) is deleted and the following substituted:

334-3.2.7 Additional Information: In addition to the requirements listed above, provide the following information with each proposed mix design submitted for verification:

1. The design traffic level and the design number of gyrations (N_{design}).
2. The source and description of the materials to be used.
3. The DOT source number and the DOT product code of the aggregate components furnished from a DOT approved source.
4. The gradation and proportions of the raw materials as intended to be combined in the paving mixture. The gradation of the component materials shall be representative of the material at the time of use. Compensate for any change in aggregate gradation caused by handling and processing as necessary.
5. A single percentage of the combined mineral aggregate passing each specified sieve. Degradation of the aggregate due to processing (particularly material passing the No. 200 sieve) should be accounted for and identified.
6. The bulk specific gravity (G_{sb}) value for each individual aggregate and RAP component, as identified in the Department's aggregate control program.
7. A single percentage of asphalt binder by weight of total mix intended to be incorporated in the completed mixture, shown to the nearest 0.1 percent.
8. A target temperature for the mixture at the plant (mixing temperature) and a target temperature for the mixture at the roadway (compaction temperature) in accordance

with ~~330~~320-6.3. Do not exceed a target temperature of 330°F for PG 76-22 asphalt binders, 320°F for ARB-12 asphalt binders, and 315°F for ARB-5 and unmodified asphalt binders.

9. Provide the physical properties achieved at four different asphalt binder contents. One of which shall be at the optimum asphalt content, and must conform to all specified physical requirements.

10. The name of the CTQP Qualified Mix Designer.

11. The ignition oven calibration factor.

12. The warm mix technology, if used.

SUBARTICLE 334-5.1.1 and 334-5.1.2(of the Supplemental Specification) is deleted and the following substituted:

334-5.1.1 Sampling and Testing Requirements: Obtain the samples in accordance with FM 1-T 168. Obtain samples at the plant of a sufficient quantity to be split into three smaller samples; one for Quality Control, one for Verification and one for Resolution testing; each sample at approximately 35 pounds. The split samples for Verification testing and Resolution testing shall be reduced in size and stored in three boxes each. The approximate size of each box must be 12 inches x 8 inches x 4 inches. Provide, label and safely store sample boxes in a manner agreed upon by the Engineer for future testing.

The asphalt content of the mixture will be determined in accordance with FM 5-563. In the event the FM 5-563 ignition oven goes out of service during production, the Contractor may elect to use a replacement oven at another location for no more than 72 hours while the oven is being repaired. The gradation of the recovered aggregate will be determined in accordance with FM 1-T 030. Volumetric testing will be in accordance with AASHTO T 312-08 and FM 1-T 209. Measure the inside diameter of gyratory molds in accordance with FM 5-585. Prior to testing volumetric samples, condition the test-sized sample for one hour plus or minus five minutes at the target roadway compaction temperature in a ~~covered~~, shallow, flat pan, such that the mixture temperature at the end of the one hour conditioning period is within plus or minus 20°F of the roadway compaction temperature. Test for roadway density in accordance with FM 1-T 166.

334-5.1.2 Acceptance Testing Exceptions: When the total combined quantity of hot mix asphalt for the project, as indicated in the plans for Type SP and Type FC mixtures only, is less than 2000 tons, the Engineer will accept the mix on the basis of visual inspection. The Engineer may require the Contractor to run process control tests for informational purposes, as defined in 334-4, or may run independent verification tests to determine the acceptability of the material.

Density testing for acceptance will not be performed on widening strips or shoulders with a width of 5 feet or less, open-graded friction courses, variable thickness overbuild courses, leveling courses, any asphalt layer placed on subgrade (regardless of type), miscellaneous asphalt pavement, bike/shared use paths, crossovers, or any course with a specified thickness less than 1 inch or a specified spread rate that converts to less than 1 inch as described in 334-1.4. Density testing for acceptance will not be performed on asphalt courses placed on bridge decks or approach slabs; compact these courses in static mode only per the requirements of 330-~~10.1.8~~7.7. In addition, density testing for acceptance will not be performed on the following areas when they are less than 1,000 feet (continuous) in length: turning lanes, acceleration lanes, deceleration lanes, shoulders, parallel parking lanes or ramps.

Density testing for acceptance will not be performed in intersections. The limits of the intersection will be from stop bar to stop bar for both the mainline and side streets. A random core location that occurs within the intersection shall be moved forward or backward from the intersection at the direction of the Engineer.

Where density testing for acceptance is not required, compact these courses (with the exception of open-graded friction courses) in accordance with the rolling procedure (equipment and pattern) as approved by the Engineer or with Standard Rolling Procedure as specified in 330-~~10.1.27.2~~. In the event that the rolling procedure deviates from the procedure approved by the Engineer, or the Standard Rolling Procedure, placement of the mix shall be stopped.

The density pay factor (as defined in 334-8.2) for LOTs where there are areas not requiring density testing for acceptance will be prorated based on a pay factor of 1.00 for the quantity (tonnage) of material in areas not requiring density testing for acceptance and the actual pay factor for the tonnage of material in areas requiring density testing.

SUBARTICLE 334-5.8 (of the Supplemental Specification) is deleted and the following substituted:

334-5.8 Surface Tolerance: The asphalt mixture will be accepted on the roadway with respect to surface tolerance in accordance with the applicable requirements of 330-~~129~~.

ARTICLE 334-7 (of the Supplemental Specification) is deleted and the following substituted:

334-7 Method of Measurement.

For the work specified under this Section (including the pertinent provisions of Sections 320 and 330), the quantity to be paid for will be the weight of the mixture, in tons. The pay quantity will be based on the project average spread rate, excluding overbuild, limited to a maximum of 105% of the spread rate determined in accordance with 334-1.4 or as set by the Engineer. The project average spread rate is calculated by totaling the arithmetic mean of the average daily spread rate values for each layer.

The bid price for the asphalt mix will include the cost of the liquid asphalt or the asphalt recycling agent and the tack coat application as directed in 300-8. There will be no separate payment or unit price adjustment for the asphalt binder material in the asphalt mix. For the calculation of unit price adjustments of bituminous material, the average asphalt content will be based on the percentage specified in 9-2.1.2. The weight will be determined as provided in 320-~~2~~ **3.2** (including the provisions for the automatic recordation system).

Prepare a Certification of Quantities, using the Department's current approved form, for the certified Superpave asphalt concrete pay item. Submit this certification to the Engineer no later than Twelve O'clock noon Monday after the estimate cut-off or as directed by the Engineer, based on the quantity of asphalt produced and accepted on the roadway per Contract. The certification must include the Contract Number, FPID Number, Certification Number, Certification Date, period represented by Certification and the tons produced for each asphalt pay item.

3340104
All Jobs