

EXPECTED IMPLEMENTATION JULY 2012

455 STRUCTURES FOUNDATION. (REV 10-25-11) (FA 12-8-11) (7-12)

SUBARTICLE 455-12.2 (Page 553) is deleted and the following substituted:

455-12.2 Prestressed Concrete Piling: Price and payment will be full compensation for the cost of furnishing and placing all reinforcing steel, predrilled holes, furnishing the material for and wrapping pile clusters with wire cable where so shown in the plans and grouting of preformed pile holes when shown in the plans.

SUBARTICLE 455-12.3 (Pages 553 and 554) is deleted and the following substituted:

455-12.3 Steel Piling: Price and payment will be full compensation for all labor, equipment, and materials required for furnishing and installing Steel Piling, including welding and painting as specified and the cost of predrilling pile holes described in 455-5.1.1. The cost of any sand or concrete fill and reinforcing steel in pipe piles will be included in the price for Steel Piling.

Bracing and other metal parts attached to or forming a part of piling or bracing and not otherwise classified, will be measured and paid for as provided in Section 460.

SUBARTICLE 455-12.4 (Page 554) is deleted and the following substituted:

455-12.4 Test Piles: Price and payment will be full compensation for all incidentals necessary to complete all the work of this item except splices, build-ups, pile extractions and preformed pile holes authorized by the Engineer and paid for under other pay items or payment methods. The cost of all additional work not listed above necessary to ensure required penetration and attain required bearing of the test piles will be included in the price bid per foot of Test Pile, including driving and all other related costs.