



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

ANANTH PRASAD, P.E.
SECRETARY

December 7, 2012

Monica Gourdine
Program Operations Engineer
Federal Highway Administration
545 John Knox Road, Suite 200
Tallahassee, Florida 32303

Re: Office of Design, Specifications
Section **005**
Proposed Specification: **0050104 Control of the Work.**

Dear Ms. Gourdine:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

These changes were proposed by Brad Bradley of the State Structures Design Office to clarify that only non-standard drainage structures require the submittal of shop drawings.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to SP965TT or trey.tillander@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4140.

Sincerely,

Signature on file

V. Y. "Trey" Tillander, III, P.E.
State Specifications Engineer

TT/dt

Attachment

cc: Florida Transportation Builders' Assoc.
State Construction Engineer

CONTROL OF THE WORK.**(REV 10-2612-67-12)**

SUBARTICLE 5-1.4.2 (Pages 32 – 33) is deleted and the following substituted:

5-1.4.2 Work Items Requiring Shop Drawings: In general, the Department requires shop drawings for items of work not fully detailed in the plans which require additional drawings and coordination prior to constructing the item, including but not limited to:

- (a) Bridge components not fully detailed in the plans, i.e. segments, steel girder details, post-tensioning details, handrails, etc.
- (b) Retaining Wall Systems
- (c) Precast Box Culverts
- (d) Non-standard *structures and components for drainage, lighting, signalization and signing* ~~structures and components~~
- (e) Building structures
- (f) *Non-standard* ~~Drainage and structures, attenuators, crash cushions~~ and other nonstructural items
- (g) Design and structural details furnished by the Contractor in compliance with the Contract
- (h) Temporary Works affecting public safety

Additional clarification for certain types of bridge structures is provided in 5-1.4.7. Other provisions of the Contract Documents may waive the requirement for submittals for certain items; i.e., items constructed from standard drawings or those complying with alternate details for prestressed members under Section 450. Review the Contract Documents to determine the submittals required.

CONTROL OF THE WORK.**(REV 12-7-12)**

SUBARTICLE 5-1.4.2 (Pages 32 – 33) is deleted and the following substituted:

5-1.4.2 Work Items Requiring Shop Drawings: In general, the Department requires shop drawings for items of work not fully detailed in the plans which require additional drawings and coordination prior to constructing the item, including but not limited to:

- (a) Bridge components not fully detailed in the plans, i.e. segments, steel girder details, post-tensioning details, handrails, etc.
- (b) Retaining Wall Systems
- (c) Precast Box Culverts
- (d) Non-standard structures and components for drainage, lighting, signalization and signing
- (e) Building structures
- (f) Non-standard crash cushions and other nonstructural items
- (g) Design and structural details furnished by the Contractor in compliance with the Contract
- (h) Temporary Works affecting public safety

Additional clarification for certain types of bridge structures is provided in 5-1.4.7. Other provisions of the Contract Documents may waive the requirement for submittals for certain items; i.e., items constructed from standard drawings or those complying with alternate details for prestressed members under Section 450. Review the Contract Documents to determine the submittals required.