

EXPECTED IMPLEMENTATION JANUARY 2014

611 ACCEPTANCE PROCEDURES FOR TRAFFIC CONTROL SIGNALS AND DEVICES.

(REV 5-14-13) (FA 8-7-13) (1-14)

ARTICLE 611-2.2 (Page 773) is deleted and the following substituted:

611-2.2 Final Acceptance: The Engineer will make inspection for final acceptance of traffic control signal and device installations as part of all work under the Contract in accordance with 5-11, only after satisfactory completion of all field tests of completed installations and on the basis of a comprehensive final field inspection of all equipment installations. Submit three copies of Form 750-010-02, Submittal Data – Traffic Control Equipment for each cabinet location, to the Engineer. The Engineer will make the final inspection with a Contractor's representative and, when applicable, a representative of the agency designated to accept maintenance responsibility. The Engineer will submit a copy of the approved form to the District Traffic Operations Engineer and place one copy in the cabinet at each location. Transfer warranties and guarantees on equipment to the Department in accordance with Section 608. For traffic signal installations, submit three completed copies of form 700-010-22, Final Acceptance of Traffic Signal Installation(s) and Transfer of Maintenance, to the Engineer.

ARTICLE 611-5.1 (Page 775) is deleted and the following substituted:

611-5.1 General Requirements: Repair or replace any defective components or work of the installations for a 90 day period after final acceptance.