



*Florida Department of Transportation*

RICK SCOTT  
GOVERNOR

605 Suwannee Street  
Tallahassee, FL 32399-0450

ANANTH PRASAD, P.E.  
SECRETARY

January 9, 2014

Chad Thompson  
Programs Operations Engineer  
Federal Highway Administration  
545 John Knox Road, Suite 200  
Tallahassee, Florida 32303

Re: State Specifications and Estimates Office  
Section **160**  
Proposed Specification: **1600302 Stabilizing.**

Dear Mr. Thompson:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

These changes were proposed by Ben Watson of the State Materials Office to reflect changes to Senate Bill 682 and Florida Statute 403.704.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to SP965DS or daniel.scheer@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Daniel Scheer, P.E.  
State Specifications Engineer

DS/cah  
Attachment

cc: Florida Transportation Builders' Assoc.  
State Construction Engineer

**STABILIZING.****(REV ~~11-920-143~~)**

SUBARTICLE 160-3.2 is deleted and the following substituted:

**160-3.2 Application of Stabilizing Material:** After substantially completing the roadbed grading operations, determine the type and quantity (if any) of stabilizing material necessary for compliance with the bearing value requirements. *Before using any Fossil Fuel Combustion Products (FFCPs), provide documentation, at the preconstruction meeting or no later than 30 days prior to delivery of FFCP's to the project, signed and sealed by the Specialty Engineer that these materials meet the requirements of 403.7047F.S.* Notify the Engineer of the approximate quantity to be added before spreading. When additive stabilizing materials are required, spread the material uniformly over the area to be stabilized.

**STABILIZING.****(REV 1-9-14)**

SUBARTICLE 160-3.2 is deleted and the following substituted:

**160-3.2 Application of Stabilizing Material:** After substantially completing the roadbed grading operations, determine the type and quantity (if any) of stabilizing material necessary for compliance with the bearing value requirements. Before using any Fossil Fuel Combustion Products (FFCPs), provide documentation, at the preconstruction meeting or no later than 30 days prior to delivery of FFCP's to the project, signed and sealed by the Specialty Engineer that these materials meet the requirements of 403.7047F.S. Notify the Engineer of the approximate quantity to be added before spreading. When additive stabilizing materials are required, spread the material uniformly over the area to be stabilized.