

**PORTLAND CEMENT CONCRETE – ACCEPTANCE SAMPLING FREQUENCY.
(REV 10-29-14) (FA 1-22-15) (1-16)**

SUBARTICLE 346-9.2 is deleted and the following substituted:

346-9.2 Sampling Frequency: As a minimum, sample and test concrete of each design mix for water to cementitious materials ratio, air content, temperature, slump and compressive strength once per LOT as defined by Table 8. When a mix design is used for a different application, the LOT is defined by the application. The Engineer will randomly verify one of every eight consecutive LOTs of each design mix based on a random number generator. The Department may perform Independent Verification testing to verify compliance with specification requirements. All QC activities, calculations, and inspections will be randomly confirmed by the Department.

TABLE 8	
Class Concrete*	LOT Size
I	one day's production
I (Pavement)	2000 square yards, or one day's production, whichever is less
II, II (Bridge Deck), III, IV, V (Special), V, VI	50 cubic yards, or one day's production, whichever is less
IV (Drilled Shaft)	50 cubic yards, or two hours between the end of one placement, and the start of the next placement, whichever is less
III (Seal)	Each Seal placement
*For any class of concrete used for roadway barrier wall, the lot size is defined as 100 cubic yards, or one day's production, whichever is less.	

346-9.2.1 Reduced Frequency for Acceptance Tests: The LOT size may represent 100 cubic yards when produced at the same mix design at the same concrete production facility for the same prime contractor and subcontractor on a given Contract. Submit test results indicating the average compressive strength is greater than two standard deviations above the specified minimum strength for that class of concrete. Base calculations on a minimum of ten consecutive strength test results for a Class IV or higher; or a minimum of five consecutive strength results for a Class III or lower.

The average of the consecutive compressive strength test results, based on the class of concrete, can be established using historical data from a previous Department project. The tests from the previous Department project must be within the last 60 calendar days or may also be established by a succession of samples on the current project. Only one sample can be taken from each LOT. Test data must be from a laboratory meeting the requirements of Section 105. Obtain Department approval before beginning reduced frequency LOT's.

If at any time a strength test is not verified or the average strength of the previous ten or five consecutive samples based on the class of concrete from the same mix design and the same production facility is less than the specified minimum plus two standard deviations, return to the maximum production quantity represented by the LOT as defined in

Table 8. Notify the Engineer that the maximum production rate is reinstated. In order to reinitiate reduced frequency, submit a new set of strength test results.