![Centennial FDOT 1915-2015 logo]

# *Florida Department of Transportation*

**RICK SCOTT**
**GOVERNOR**

605 Suwannee Street
Tallahassee, FL  32399-0450

**JIM BOXOLD**
**SECRETARY**

December 22, 2015

Khoa Nguyen
Director, Office of Technical Services
Federal Highway Administration
3500 Financial Plaza, Suite 400
Tallahassee, Florida 32312

Re:     State Specifications Office
        Section **911**
        Proposed Specification: **9110301 Base and Stabilized Base Materials**

Dear Mr. Nguyen:

We are submitting, for your approval, two copies of the above referenced Supplemental
Specification.

The changes are proposed by John Shoucair of the State Materials Office to correct an error in
the Limerock Bearing Ratio for Recycled Concrete Aggregate (RCA) in Table 911-1.

Please review and transmit your comments, if any, within two weeks. Comments should be sent
via email to daniel.scheer@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Signature on file

Daniel Scheer, P.E.
State Specifications Engineer

DS/ot
Attachment
cc:     Florida Transportation Builders' Assoc.
        State Construction Engineer

**BASE AND STABILIZED BASE MATERIALS.**
**(REV 11-3-15)**

SUBARTICLE 911-3.1 is deleted and the following substituted:

**911-3.1 Limerock Bearing Ratio (LBR):** Materials shall meet the requirements in Table 911-1 in accordance with FM 5-515:

| Table 911-1 Limerock Bearing Ratio (LBR) | |
|---|---|
| Material | Requirement |
| Limerock | Average Results per LOT - 100, minimum Individual Results - 90, minimum |
| Shell | |
| Shell-Rock | |
| Cemented Coquina Shell | |
| RCA | ~~Average Results per LOT~~*Individual Result* - 150, minimum |

**BASE AND STABILIZED BASE MATERIALS.**
**(REV 11-3-15)**

SUBARTICLE 911-3.1 is deleted and the following substituted:

**911-3.1 Limerock Bearing Ratio (LBR):** Materials shall meet the requirements in Table 911-1 in accordance with FM 5-515:

| Table 911-1 | |
|---|---|
| Limerock Bearing Ratio (LBR) | |
| Material | Requirement |
| Limerock | Average Results per LOT - 100, minimum<br>Individual Results - 90, minimum |
| Shell | |
| Shell-Rock | |
| Cemented Coquina Shell | |
| RCA | Individual Result - 150, minimum |