

EXPECTED IMPLEMENTATION JULY 2016

102 MAINTENANCE OF TRAFFIC. (REV 9-21-15) (FA 10-26-15) (7-16)

SUBARTICLE 102-11.10 is deleted and the following substituted:

102-11.10 Barrier Delineators: The number of barrier delineators, installed on top of barrier wall and vehicular LCDs, used on the project, meeting the requirements of the Design Standards and Section 705.

SUBARTICLE 102-13.10 is deleted and the following substituted:

102-13.10 Barrier Delineators: No separate payment will be made for barrier delineators installed on top of temporary barrier wall and vehicular LCDs. The cost of furnishing, installing and maintaining the barrier delineators will be included in the cost of the temporary barrier wall and vehicular LCDs.