

# EXPECTED IMPLEMENTATION JULY 2016

## 450 PRECAST PRESTRESSED CONCRETE CONSTRUCTION. (REV12-17-15) (FA 12-21-15) (7-16)

SUBARTICLE 450-2.3 is deleted and the following substituted:

**450-2.3 Product Certification:** Ensure the QC inspector inspects all completed products at the plant not less than 24 hours before shipment to verify that all Contract Documents requirements are met. Upon verification that all Contract Document requirements have been met and all necessary repairs have been satisfactorily completed, the product will be stamped with the approved QC Manager stamp identified in the Producer QC Plan.

With each monthly request submitted for payment, attach a certification stating that the listed precast prestressed products have been produced under the Producer QC Plan and meet the Contract Document requirements. Ensure the certification is signed by a legally responsible person of the plant and is submitted on the plant's letterhead.