

**CONCRETE GUTTER, CURB ELEMENTS, AND TRAFFIC SEPARATOR.
(REV 7-29-16) (7-17)**

ARTICLE 520-1 is deleted and the following substituted:

520-1 Description.

Construct or reconstruct portland cement concrete curb and gutter, concrete traffic separator, valley gutter, special concrete gutter, curb for sidewalk curb ramps and driveways, and any other types of concrete curb not specified in other Sections, and as shown in the current edition of the Design Standards, or as directed by the Engineer.

ARTICLE 520-7 is expanded by the following new Subarticle:

520-7.3 Clean-up: Remove from the job site any surplus or discarded materials or rubbish and restore the job site area to a condition acceptable to the Engineer, upon completion of work, and before final payment is made. Disposal of concrete rubble, unless otherwise specified in writing by the Engineer, will be included in the contract unit price.

ARTICLE 520-12 is expanded by the following new Subarticle:

520-12.6 Payment Items: Payment will be made under the items specified in the Bid Price Proposal.