

# EXPECTED IMPLEMENTATION JANUARY 2018

## 425 INLETS, MANHOLES, AND JUNCTION BOXES. (REV 4-28-17) (FA 5-8-17) (1-18)

SUBARTICLE 425-2.2 is deleted and the following substituted:

**425-2.2 Mortar:** For brick masonry, make the mortar by mixing one part portland cement to three parts sand. Miami Oolitic rock screenings may be substituted for the sand, provided the screenings meet the requirements of 902-5.2.3 except for gradation requirements. Use materials passing the No. 8 sieve that are uniformly graded from coarse to fine. Submit documentation, from a Department approved mine or a Department approved concrete plant, confirming the sand or sand substitute meets the requirements of 902-3.2.

Masonry cement may be used in lieu of the above-specified mortar provided it is delivered in packages properly identified by brand name of manufacturer, net weight of package, and whether it is Type 1 or Type 2, and further provided that it has not been in storage for a period greater than six months.

D

R

A

F

T