

EXPECTED IMPLEMENTATION JULY 2018

110 CLEARING AND GRUBBING (REV 10-30-17) (FA 1-1-18) (7-18)

ARTICLE 110-7 is deleted and the following substituted:

110-7 Removal of Existing Concrete.

Remove and dispose of existing rigid portland cement concrete pavement, sidewalk, slope pavement, ditch pavement, curb, and curb and gutter, etc., where shown in the Plans.

Remove all gravity walls, noise/sound walls, retaining walls, MSE walls, perimeter walls, and roadway concrete barriers, where shown in the Plans. All ancillary elements of these concrete features being removed including, but not limited to, leveling pads, copings, reinforcing steel or straps, footings, etc, are incidental and included in the cost of the removal.