

# **EXPECTED IMPLEMENTATION JULY 2018**

## **413 SEALING CRACKS AND CONCRETE STRUCTURE SURFACES (REV 10-16-17) (FA 12-13-17) (7-18)**

SUBARTICLE 413-3.3.3 is deleted and the following substituted:

**413-3.3.3 Raised Pavement Markers (RPMs):** Protect by masking or clean after application, all existing RPMs affected by the application of the methacrylate. Alternatively, remove and replace such RPMs as indicated in the Contract Documents.

**D**

**R**

**A**

**F**