

EXPECTED IMPLEMENTATION JULY 2018

452 PRECAST SEGMENTAL BRIDGE CONSTRUCTION (REV 10-30-17) (FA 1-1-18) (7-18)

ARTICLE 452-9 is deleted and the following substituted:

452-9 Traffic Railing and Median Setting.

Prior to forming the concrete traffic railings, accurately establish the as-constructed gutter line elevations at intervals not exceeding 10 feet. Then form the base of the traffic railing and median to provide an inside vertical face which extends from the surface of the concrete structure to an elevation located 3 inches (or as shown in the Plans) above the theoretical gutter line elevations. Maintain the plan vertical height of the traffic railings as a minimum when variations exist between the plan profile and the actual profile of the gutter.

D

R

A

F

T