

EXPECTED IMPLEMENTATION JULY 2018

561 COATING EXISTING STRUCTURAL STEEL (REV 11-6-17) (FA 1-1-18) (7-18)

SUBARTICLE 561-4.1 is deleted and the following substituted:

561-4 Quality Control (QC).

561-4.1 Field Preparation and Application: Submit a current Corporate Q C Plan approved by SSPC under the SSPC QP1 and SSPC QP2 certifications as appropriate and a site specific Coating Plan to the Engineer at least 14 calendar days prior to beginning coatings work. Do not begin coatings work until the site specific Coating Plan has been approved by the Engineer.

Prepare a traffic control plan for each phase of construction activities signed and sealed by the Contractor's Engineer of Record in accordance with the FDOT Design Manual. Do not begin work until the traffic control plan is approved by the Engineer. Maintain traffic in accordance with Section 102.

For work over navigable waters, submit a work plan to the United States Coast Guard including any scheduled restrictions to navigation channels or marine traffic. Obtain Coast Guard approval at least 30 days in advance of any restrictions.