

DETECTABLE WARNINGS

(REV 11-6-18) (7-20)

SUBARTICLE 527-3.1 is deleted and the following substituted:

527-3.1 Surface Preparation and Installation: Completely remove existing detectable warning material, (to include adhesives, mechanical fasteners, etc.). Prepare the surface in accordance with the manufacturer's recommendations. Use only products and materials appropriate for the surface on which they will be applied. Install in accordance with the manufacturer's instructions, using materials and equipment recommended and approved by the manufacturer. For surface applied tiles or mats, use adhesives applied over the entire surface and mechanical fasteners.

SUBARTICLE 527-5 is deleted and the following substituted:

527-5 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section, including all labor, surface preparation, materials and incidentals necessary to complete the work. For repairs and replacements, removal of the existing detectable warnings will be included in the cost of new detectable warnings. Payment will be made under:

Item No. 527- 2- Detectable Warnings– square foot.