



Florida Department of Transportation

RON DESANTIS
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

KEVIN J. THIBAUT, P.E.
SECRETARY

November 19, 2019

Khoa Nguyen
Director, Office of Technical Services
Federal Highway Administration
3500 Financial Plaza, Suite 400
Tallahassee, Florida 32312

Re: State Specifications Office
Section: **SP101**
Proposed Specification: **SP1010202LS Mobilization.**

Dear Mr. Nguyen:

We are submitting, for your approval, two copies of the above referenced Special Provision.

The changes are proposed by Ashley Anderson from the Office of Construction to provide clarification on partial payments for Mobilization.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to daniel.strickland@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Signature on file

Daniel Strickland, P.E.
State Specifications Engineer

DS/jj

Attachment

cc: Florida Transportation Builders' Assoc.
State Construction Engineer

MOBILIZATION (LUMP SUM).
(REV 10-17-19)

SUBARTICLE 101-2.2 is deleted and the following substituted:

SECTION 101
MOBILIZATION

101-1 Description.

Perform preparatory work and operations in mobilizing for beginning work on the project, including, but not limited to, those operations necessary for the movement of personnel, equipment, supplies, and incidentals to the project site and for the establishment of temporary offices, buildings, safety equipment and first aid supplies, and sanitary and other facilities.

Include the costs of bonds and any required insurance and any other preconstruction expense necessary for the start of the work, excluding the cost of construction materials.

101-2 Basis of Payment.

101-2.1 General: The work and incidental costs specified as being covered under this Section will be paid for at the lump sum prices for the items of mobilization included in the Schedule of Values.

101-2.2 Partial Payments: When the Notice to Proceed has been issued, partial payments will be made in accordance with the following:

For Contracts of 120 Contract days duration or less, partial payment will be made at 50% of the Mobilization amount shown in the Schedule of Values per month for the first two months until 100% of the Mobilization amount shown in the Schedule of Values is paid. For Contracts in excess of 120 Contract days duration, partial payment will be made at 25% of the Mobilization amount shown in the Schedule of Values per month for the first four months until 100% of the Mobilization amount shown in the Schedule of Values is paid. In no event shall more than 50% of the Mobilization amount shown in the Schedule of Values be paid prior to commencing construction on the project site.

Total partial payments for Mobilization ~~on any project, including when more than one project or job is included in the Contract,~~ will be limited to 10% of the original Contract amount ~~for that project~~. Any remaining amount will be paid at Final Acceptance. ~~upon completion of all work on the Contract.~~

Retainage, as specified in 9-5, will be applied to all partial payments.

Partial payments made on this item will in no way act to preclude or limit any of the provisions for partial payments otherwise provided for by the Contract.

MOBILIZATION (LUMP SUM).
(REV 10-17-19)

SUBARTICLE 101-2.2 is deleted and the following substituted:

SECTION 101
MOBILIZATION

101-1 Description.

Perform preparatory work and operations in mobilizing for beginning work on the project, including, but not limited to, those operations necessary for the movement of personnel, equipment, supplies, and incidentals to the project site and for the establishment of temporary offices, buildings, safety equipment and first aid supplies, and sanitary and other facilities.

Include the costs of bonds and any required insurance and any other preconstruction expense necessary for the start of the work, excluding the cost of construction materials.

101-2 Basis of Payment.

101-2.1 General: The work and incidental costs specified as being covered under this Section will be paid for at the lump sum prices for the items of mobilization included in the Schedule of Values.

101-2.2 Partial Payments: When the Notice to Proceed has been issued, partial payments will be made in accordance with the following:

For Contracts of 120 Contract days duration or less, partial payment will be made at 50% of the Mobilization amount shown in the Schedule of Values per month for the first two months until 100% of the Mobilization amount shown in the Schedule of Values is paid. For Contracts in excess of 120 Contract days duration, partial payment will be made at 25% of the Mobilization amount shown in the Schedule of Values per month for the first four months until 100% of the Mobilization amount shown in the Schedule of Values is paid. In no event shall more than 50% of the Mobilization amount shown in the Schedule of Values be paid prior to commencing construction on the project site.

Total partial payments for Mobilization will be limited to 10% of the original Contract amount. Any remaining amount will be paid at Final Acceptance.

Retainage, as specified in 9-5, will be applied to all partial payments.

Partial payments made on this item will in no way act to preclude or limit any of the provisions for partial payments otherwise provided for by the Contract.