Effective: May 19, 2005 Revised: August 28, 2018 January 1, 2021

SECTION 8.3 Volume II

PRESTRESSED CONCRETE PRODUCERS QUALITY CONTROL RELATED TO MAJOR PRODUCT DEFECTS

8.3.1. PURPOSE

The purpose of this procedure is to establish a standard method for evaluating the effectiveness of Prestressed Concrete Producer (Plant) Qquality Ceontrol (QC) processes for minimizing the incidence of major defects in prestressed concrete products Products. This evaluation process requires monitoring the rate of major production defects that occur in prestressed concrete products; using these major defects rates as a basis for evaluating the effectiveness of the Plant's QC efforts; and taking action that will improve the Plant's QC efforts when they are below the satisfactory level.

8.3.2. AUTHORITY

334.044(2), 334.044(10)(a), and 334.048 Florida Statutes

8.3.3. REFERENCES

Florida Department of Transportation Standard Specifications for Road and Bridge Construction Section 450 Precast Prestressed Concrete Construction

Code of Federal Regulations (CFR), Federal-Aid Policy Guide (FAPG), Subchapter G – Engineering and Traffic Operations, Part 637 – Construction Inspection and Approval, Subpart B – Quality Assurance Procedures for Construction Sections

8.3.4. SCOPE

This procedure is used by the Plants to monitor and ensure that the major defect rate of products produced cast does not exceed the established limits. Primary offices that are affected by this procedure include the District Materials and Research Offices (DMRO), State Materials Office (SMO), District Construction Offices (DCO), State Construction Office (SCO), District Structures Design Office (SDO), State-Structures Design Office (SDO).

Topic No.: 675-000-000

Materials Manual Effective: May 19, 2005
Precast/Prestressed Concrete Products Revised: August 28, 2018 January 1, 2021

8.3.5. GENERAL INFORMATION

Major defects may occur in prestressed concrete products Products during the production process. These defects are usually correctable and the Department can accept the Pproduct; however, the Department does not consider the quality of a corrected Pproduct to be as good as the quality of a Pproduct that needs no correction. If major defects are identified, the requirements of FDOT Specifications Section 6 will be followed. Since the Department seeks to place products Products with the very best quality into service whenever possible, the number of corrected or defective products Products with major defects must be kept to a minimum. To encourage Plants to establish and maintain efforts that minimize major defects, the Department compiles major defect rates on a semiannual basis for each prestressed concrete Peroduct group at each Plant and these major defect rates are used as the basis for establishing a major defect rate limit. A defect rate limit is the defect rate that a Plant must stay below to achieve the level of Peroduct quality that is acceptable to the Department.

8.3.6. MONITORING MAJOR DEFECTS

8.3.6.1. Plant and DMRO Responsibilities

Plants are required to submit to the DMRO, the semiannual compilation of the major deficiency defect data for each category and group of products Products. Ensure that the Plant's QC pPlan addresses this requirement, as described in FDOT Specifications Section 450. Each DMRO will verify and compile the submitted major defect rate data for Plants which they are responsible for verification inspection and testing within their jurisdiction. The compiled data must be summarized as shown on the attached sample spreadsheet referred to as a Prestressed Concrete Product Defect Data Table (Table 8-3-1), every 6 months, referred to as the monitoring periods, which are from January 1st to June 30th and from July 1st to December 31st of each year.

If the Plant believes a major defect is caused by a design error and not a Plant error, the Project Administrator (PA) and the DMRO prestressed concrete personnel must determine whether they agree with the Plant. If they disagree with the Plant, the Plant can appeal to the District Construction Engineer (DCE) and District Materials and Research Engineer (DMRE) who should consult with the District SDO and/or State-SDO before making a final decision. Until a final decision is made by the Department about the defect in question, it will not be reported in the *Prestressed Concrete Product Defect Data Table*.

If the DMRO representative determines that a defect is major and the Plant disagrees, then the determination may be appealed to the DCE and DMRE for final determination. Until a final determination is made by the Department about

Prestressed concrete products Products are organized by Product groups that have similar casting, stressing and handling characteristics in the **Prestressed**Concrete Product Defect Data Table:

A major defect rate limit will be established for each Product group based on this criteria. therefore, have defect rates and a defect limit that are also characteristic of the group.

The information gathered during a monitoring period for 6 months for each product group includes the following:

- 1) Total number of products Products produced cast.
- 2) Number of major defects, by defect type, in the <u>productsProducts</u> <u>producedcast</u>.
- 3) Total number of major defects, which is the summation of all major defect types in (2).
- 3)4) The defect rate, which is computed by dividing the value in (3) above (total number of major defects) by the value in (1) above (total number of Products cast). For example: if 100 Products are cast and 20 products have major defects, then the defect rate is computed by dividing 20 by 100 which results in a major defect rate of 20 percent.
- 4) The defect rate, which is computed by dividing the value in (3) above (total number of major defects) by the value in (1) above (total number of products Products produced). For example: if 100 products Products are produced and these have a total number of major defects of 20 then the defect rate is computed by dividing 20 by 100 which results in 1/5 or 0.20 defects per product produced.

Within 14 days after each 6-monthmonitoring period data gathering period expires, the DMRO must electronically forward provide the *Prestressed Concrete Product Defect Data Table* for each Plant in their respective jurisdiction district to the SMO. Only major defects, as defined in *FDOT Specification Section 450* are to be be entered into the *Prestressed Concrete Product Defect Data Table* included, with the following qualifications:

1) Only include major defects on Products that were cast during the indicated monitoring period. If major defects are discovered on a Product that was cast during the monitoring period but discovered after the monitoring period ended, provide the Product and major defect information to the DMRO upon discovery of the information from the Plant.

- Do not include the bottom flange spalls of the skewed beams which are caused by the effects of beam camber.
- Do not include major defects caused by the degree of skew if the skew angle (the angle between the longitudinal axis and the skewed end face of the beam) is less than the following limit:
 - a. Type II, III and IV AASHTO Beams 55 degrees
 - b. Type V and VI AASHTO Beams 65 degrees
 - c. Florida-I Beams and Bulb-T Beams 70 degrees
- 3)—Do not include uncorrected major defects that are revealed during inspection after delivery to the project site, in the Prestressed Concrete Product Defect Data Table. The PA must report the defect to the DMRO prestressed concrete personnel who should evaluate whether the Plant is in compliance with the QC Pplan. If the Plant is not in compliance with the QC Pplan, appropriate action must be taken by the DMRO prestressed concrete personnel.

4)

- 5) Do not include a major defect that is caused by a design error, as determined by the Department and not by Plant error, in the Prestressed Concrete Product Defect Data Table. The PA should report to the DDistrict SDO and/or State SDO.
- 6) When an individual component (beam, pile or slab) has multiple major defects of the same type, they must be considered as one defect for reporting in the Prestressed Concrete Product Defect Data Table. For example: if an individual pile has 3 spalls, 1 chip and 2 cracks, these must be reported in the Prestressed Concrete Product Defect Data Table as 1 spall, 1 chip and 1 crack.

8.3.6.2. SMO Responsibilities

Prior to the end of the monitoring period, the SMO will provide the current Prestressed Concrete Product Defect Data Table to the DMROs for distribution to the Plants within their respective jurisdiction.

Upon the receipt of the data in accordance with 8.3.6.1, from each DMRO, the SMO enters the statewide major defect data into an electronic version of the Prestressed Concrete Product Defect Data Summary Table (Table 8-3-2) and forwards sends it to the DMROs for actions as specified in 8.3.8. This information will be used by the SMO to establish and modify the defect rate limit for each product group.

8.3.7. DEFECT RATE LIMITS

Precast/Prestressed Concrete Products Revised: August 28, 2018 January 1, 2021

The following are the established <u>major</u> defect rate limit for each category of <u>productsProducts</u>:

Effective: May 19, 2005

A. Piles: 5 percent

B. Slabs: 5 percent

C. Beams: 15 percent

The DMRO will ensure that the Plant's QC Pplan includes a statement to address the major defect rate limits and the Plant's efforts to maintain the major defect rate below the limit.

8.3.8. ACTIONS RELATED TO THE DEFECT RATE LIMIT

During monthly weekly meetings with the Plant and DMRO prestressed concrete personnel, the DMRO prestressed concrete personnel will discuss the current major defect rates with the Plant's QC MManager. The discussion shall include the Plant's action or QC pPlan modification regarding the major defect rates reduction, especially for the products Products which defect rates are approaching their limits before the end of the semiannual monitoring period.

When a Plant exceeds the established <u>major</u> defect rate limit, the DMRO must take action to encourage the Plant to improve <u>the QC</u> procedures. If procedures are not improved; the DMRO must suspend the Plant's QC <u>pPlan</u>. Actions to be taken are related to the severity of the Plant's unsatisfactory QC, <u>including and include</u> the following three levels with their definition and corresponding action:

Level 1: Major Defect rate limit exceeded during one monitoring period

Definition: The Plant's <u>major</u> defect rate has exceeded the limit for one monitoring period, but did not exceed the limit during <u>any of</u> the previous <u>three</u> <u>monitoring</u> periods.

Action Required: The DMRO must send a notice to the Plant and may ask for an amendment to the QC pPlan describing the Plant's increased QC processes for detecting and eliminating major defects.

<u>Level 2:</u> <u>Major</u> <u>Dd</u>efect rate limit exceeded for <u>two</u> consecutive monitoring periods

Definition: The Plant's <u>major</u> defect rate has exceeded the limit for <u>two</u> consecutive monitoring periods or for any 2 periods out of 4 consecutive <u>monitoring</u> periods.

Action Required: The DMRO must issue a <u>major</u> defect rate warning letter notifying the Plant that they are out of compliance with their QC pPlan. This will require the Plant to immediately re-submit the QC Pplan which must address a

Topic No.: 675-000-000 Materials Manual

Materials Manual Effective: May 19, 2005
Precast/Prestressed Concrete Products Revised: August 28, 2018 January 1, 2021

method for reducing the <u>major</u> defect rate to below the established <u>major</u> defect rate limit. In addition, the frequency of the QC, <u>and</u> verification, and independent assurance inspection and testing must be increased for a period not to exceed 6 monthsthe Product group and defect type that exceeded the <u>major defect rate limit</u>. The duration is at the discretion of the DMRE and will be commensurate with the seriousness of QC lapses. The increased frequency of the QC, <u>and</u> verification, <u>and independent assurance</u> inspection <u>and testing</u> will be reduced to normal when a <u>revised QC pPlan has been approved and</u> the DMRO is confident that the revised QC procedures will result in a <u>major</u> defect rate below the established <u>major</u> defect rate limit.

<u>Level 3:</u> <u>Major</u> <u>Pd</u>efect rate limit exceeded for three consecutive monitoring periods

Definition: The Plant's <u>major</u> defect rate has exceeded the limit for three consecutive monitoring periods or for any 3 periods out of 4 consecutive periods.

Action Required: The DMRO must suspend the Plant's QC PPlan and notify the Plant that their QC Pplan has been suspended until the DMRE determines that improved QC procedures will result in major defect rates that can be sustained below the established major defect rate limit for an extended period of time. During the suspension period, the Plant will not be permitted to produce cast any products Products for the pProduct group in question. Rescinding the suspension will require approval of a revised QC Pplan along with increased rates of QC₋ and verification and independent assurance inspection and testing for a duration to be determined by the DMRE. If the Plant disagrees with the duration or imposition of the suspension, an appeal may be made to the Director, State Materials Office and suspension must not be imposed until the appeal process is complete. The DMRE may waive the suspension of the Plant's QC pPlan with approval of both the Director, Office of Construction and the Director, State Materials Office, when production of components for the group in question, and for a specific project, is critical for that project's time completion.

At the discretion of the DMRE, the actions required by the DMRO for a Plant exceeding the <u>major</u> defect rate limit may be waived if the <u>major</u> defect rate limit for a single category of <u>P</u>product as specified in 8.3.7 is exceeded as the result of one major <u>pP</u>roduct defect in that category. This exception would also be permitted if the total number of <u>products Products</u> in a category, as specified in 8.3.7, is less than 20.

Precast/Prestressed Concrete ProductsProducts

TABLE 8-3-1
PRESTRESSED CONCRETE PRODUCT DEFECT DATA TABLE

	NU	MBER OF PRESTRESS	ED CONCRETE PR								THRU		Plant No	
Product	Category		Total Product										Total	
Category	Group	Product Name	Produced	1	2	3	4	5	6	7	8	9**	Defective	% Defective
(1) PILES		14" sq. Piles												
		18" sq. Piles												
	Group 1A	20" sq. Piles												
		24" sq. Piles												
		30" sq. Piles												
											Group	1A Totals		
	GP 1B	30"/36" Voided												
	GP 1C	Sheet Piles												
Cated	GP 1D	Cylinder Piles												
	orv (1) Prod	ducts Cast Total			l .					Category	(1) Defe	cts Total		
Juliog		AASHTO II						1	Ī		1 7 2 3 1 3		<u> </u>	
	Group 2A	AASHTO III							1					
		AASHTO IV												
			•	Group 2A Totals										
	Group 2B	AASHTO V												
		AASHTO VI												
	•						•				Group	2B Totals		
	Group 2C	72 Bulb-T												
ļ		78 Bulb-T												
											Group	2C Totals		
(2) BEAMS	Group 2D	U Beams												
	Group 2E	36" FIB											İ	
		45" FIB												
		54" FIB												
		63" FIB												
		72" FIB												
		78" FIB												
		84" FIB												
		96" FIB												
											Group	2E Totals		
	Group 2F	Other Beams***												
Categ	ory (2) Prod	lucts Cast Total								Category	(2) Defe	cts Total		
(3) SLABS	Group 3A	PS Slab												
	Group 3B	PS + PT Slab												
Categ	ory (3) Prod		Category (3) Defects Total											
Totals		lucts Cast/Defective									<u> </u>			
		CATION VIOLATIONS**	**											
Defective Ty		- Spalls. 2 - Chips. 3 - Ho		c 5 Dim	oncional Do	viations 6	Boarings		!	!	,			!

^{*}Defective Types:

Effective: May 19, 2005

Revised: August 28, 2018 January 1, 2021

^{1 -} Spalls, 2 - Chips, 3 - Honeycomb, 4 - Cracks, 5 - Dimensional Deviations, 6 - Bearings

⁷⁻ Reinforcement Errors, 8 - Materials Defect, 9 - Other Defective

^{**(9} Other Defective) Attach a Description of the Defective Type(s)

^{***(}Group 2F Other Beams) Attach a Description of the Type(s) of Beam(s)

^{****((4)} Specification Violations) Attach a Description of the Specification Violation(s)

TABLE 8-3-2
PRESTRESSED CONCRETE PRODUCT DEFECT DATA SUMMARY TABLE

		FK	ESIKE	:33ED	CONC	KEIE	PRUL	JUCIL	CLEC	I DAI	A SUIV	IIVIAKI	IADI	<u>-</u>		
PRESTRESSE	D C	ONCRE	TE PROD	OUCTS N	IAJOR D	EFECT D	ATA SU	MMARY	TABLE -	6 Month	Period			thru		
	G	DISTRICT 1 & 7		DISTRICT 2			DISTRICT 3			DISTRICT 4 & 6		DISTRICT 5		5		
CATEGORY	R O U P	Total Produced	Total Defective	Defect Rate												
	В															
1 PILES	С															
	D															
CATEGORY TOTALS																
	Α															
	В															
2 BEAMS	С															
BEANO	D															
	E F															
CATEGORY TOTA	LS															
3 SLABS	Α															
OLADO	В															
CATEGORY TOTA														ļ		

^{# 1}A - Square Piles (inches square): 14, 18, 20, 24, and 30

Effective: May 19, 2005

Revised: August 28, 2018 January 1, 2021

¹B - Square Piles (inches square): 30 & 36 Voided

¹C - Sheet Piles: all sizes

¹D - Cylinder Piles

²A - AASHTO Beams: Type II, III, IV

²B - AASHTO Beams: Type V and VI

 $^{2\}text{C}$ - Bulb-T Beams:72" and 78"

²D - Florida U Beams (FUB)

²E - Florida I Beams (FIB)

²F - All Other Types of Beams

³A - Prestressed Slabs

³B - Prestressed and Post-tensioned Slab