

DETECTABLE WARNINGS.
(REV 12-16-24) (FY 2025-26)

ARTICLE 527-3 is deleted and the following substituted:

527-3 Construction Requirements.

Prepare the surface, including complete removal of existing detectable warning material if present, including adhesives, bolts, tiles, or composites remaining from previous installations. Install detectable warnings in accordance with the manufacturer's installation instructions, using materials and equipment recommended and approved by the manufacturer. Construct in accordance with Standard Plans, Index 522-002.

Open the walking surface to pedestrian traffic within 72 hours for uncured concrete surfaces. Immediately open the walking surface to pedestrian traffic for asphalt and existing concrete surfaces.

Surface color and texture shall be complete and uniform. Detectable warnings will be securely installed as recommended by the manufacturer and free from lifting, cracking, missing or partial domes, and with no significant defects. Surfaces shall not deviate more than 0.10" from a true plane.

ARTICLE 527-4 is deleted and the following substituted:

527-4 Method of Measurement.

Detectable warnings will be paid per square foot of furnished, installed and accepted detectable warnings.

ARTICLE 527-5 is deleted and the following substituted:

527-5 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section, including all labor, surface preparation, removal of existing removable or surface applied detectable warning material from previous installations which may include adhesives, bolts, tiles or composites, and the equipment, and incidentals necessary to complete the work.

Payment will be made under:

Item No. 527- 2- Detectable Warnings– square foot.