Florida Department of Transportation

RON DESANTIS
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JARED W. PERDUE, P.E.
SECRETARY

June 23, 2026

Daniel Holt, PE, PTOE
Director, Project Delivery
Director, Technical Services
FHWA
400 West Washington Street, Suite 4200
Orlando, FL 32801

Re: State Specifications Office
Section: 105
Proposed Specification: **1050102 Contractor Quality Control General Requirements**

Dear Mr. Holt:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Oliver Chung to add references to the Materials Manual Section 11.1 Volume II.

Please review and transmit your comments, if any, within two weeks (10 business days). Comments should be sent via email daniel.strickland@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at (850) 414-4130.

Sincerely,

Signature on File

Daniel Strickland, P.E.
State Specifications Engineer

DS/am
Attachment
cc: Florida Transportation Builders' Assoc.
State Construction Engineer

CONTRACTOR QUALITY CONTROL GENERAL REQUIREMENTS
(REV 3-30-26)

SUBARTICLE 105-1.2.3 is deleted and the following substituted:

105-1.2.3 Notification of Placing Order: Order materials sufficiently in advance of their incorporation in the work to allow time for sampling, testing and inspection. Notify the Engineer prior to placing orders for materials.

Submit to the Engineer a fabrication schedule for all items requiring commercial inspection at least 30 days before beginning fabrication. These ~~items include steel bridge components, moveable bridge components, pedestrian bridges, castings, forgings, structures erected either partially or completely over the travelled roadway or mounted on bridges as overhead traffic signs (some of these may be further classified as cantilevered, overhead trusses, or monotubes)~~ include items listed in Table 4 of Materials Manual Section 11.1 Volume II or any other item identified as ~~an item~~requiring commercial inspection in the Contract Documents.

ARTICLE 105-3 is deleted and the following substituted:

105-3 Quality Control Program.

Certain operations require personnel with specific qualifications. Certain materials require production under an approved Quality Control (QC) Plan to ensure that these materials meet the requirements of the Contract Documents. Applicable materials include hot mix asphalt, portland cement concrete (structural), earthwork, cementitious materials, ~~timber,~~ steel and miscellaneous metals, galvanized metal products, prestressed and/or precast concrete products, drainage products, and fiber reinforced polymer products. For all applicable materials included in the Contract, submit a QC Plan prepared in accordance with the requirements of this Section to the Engineer. Do not incorporate any of these materials into the project prior to the Engineer's approval of the QC Plan.

~~Steel and Miscellaneous Metal products, including aluminum, are defined as the metal components of bridges, including pedestrian and moveable bridges, overhead and cantilevered sign supports, ladders and platforms, bearings, end wall grates, roadway gratings, drainage items, expansion joints, roadway decking, shear connectors, handrails, galvanized products, fencing, guardrail, light poles, high mast light poles, standard mast arm assemblies and Monotube assemblies, stay in place forms, casing pipe, strain poles, fasteners, connectors and other hardware.~~Steel and Miscellaneous Metal products are defined in Table 1 of the Materials Manual Section 11.1 Volume II.

SUBARTICLE 105-4.2.1 is deleted and the following substituted:

105-4.2.1 Hot Mix Asphalt, Portland Cement Concrete (Structural), Earthwork, Cementitious Materials, ~~Timber,~~ Steel and Miscellaneous Metals, Galvanized Metal Products, Prestressed and/or Precast Concrete Products, Drainage Products, and Fiber Reinforced Polymer Products Quality Control Program: Have an accepted Producer

Quality Control Program, developed in accordance with this Section, during the production of materials to be used on Department projects.

SUBARTICLE 105-4.3.1 is deleted and the following substituted:

105-4.3.1 State Materials Office (SMO): Producers of cementitious materials, steel and miscellaneous metals, galvanized metal products, aggregates, ~~timber,~~ flexible pipe, and fiber reinforced polymer (FRP) products must submit their proposed Producer Quality Control Program to the SMO for review and acceptance.

CONTRACTOR QUALITY CONTROL GENERAL REQUIREMENTS
(REV 3-30-26)

SUBARTICLE 105-1.2.3 is deleted and the following substituted:

105-1.2.3 Notification of Placing Order: Order materials sufficiently in advance of their incorporation in the work to allow time for sampling, testing and inspection. Notify the Engineer prior to placing orders for materials.

Submit to the Engineer a fabrication schedule for all items requiring commercial inspection at least 30 days before beginning fabrication. These include items listed in Table 4 of Materials Manual Section 11.1 Volume II or any other item identified as requiring commercial inspection in the Contract Documents.

ARTICLE 105-3 is deleted and the following substituted:

105-3 Quality Control Program.

Certain operations require personnel with specific qualifications. Certain materials require production under an approved Quality Control (QC) Plan to ensure that these materials meet the requirements of the Contract Documents. Applicable materials include hot mix asphalt, portland cement concrete (structural), earthwork, cementitious materials, steel and miscellaneous metals, galvanized metal products, prestressed and/or precast concrete products, drainage products, and fiber reinforced polymer products. For all applicable materials included in the Contract, submit a QC Plan prepared in accordance with the requirements of this Section to the Engineer. Do not incorporate any of these materials into the project prior to the Engineer's approval of the QC Plan.

Steel and Miscellaneous Metal products are defined in Table 1 of the Materials Manual Section 11.1 Volume II.

SUBARTICLE 105-4.2.1 is deleted and the following substituted:

105-4.2.1 Hot Mix Asphalt, Portland Cement Concrete (Structural), Earthwork, Cementitious Materials, Steel and Miscellaneous Metals, **Galvanized Metal Products, Prestressed and/or Precast Concrete Products, Drainage Products, and Fiber Reinforced Polymer Products Quality Control Program:** Have an accepted Producer Quality Control Program, developed in accordance with this Section, during the production of materials to be used on Department projects.

SUBARTICLE 105-4.3.1 is deleted and the following substituted:

105-4.3.1 State Materials Office (SMO): Producers of cementitious materials, steel and miscellaneous metals, galvanized metal products, aggregates, flexible pipe, and fiber reinforced polymer (FRP) products must submit their proposed Producer Quality Control Program to the SMO for review and acceptance.