Florida Department of Transportation

RON DESANTIS
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JARED W. PERDUE, P.E.
SECRETARY

August 20, 2026

Daniel Holt, PE, PTOE
Director, Project Delivery
Director, Technical Services
FHWA
400 West Washington Street, Suite 4200
Orlando, FL 32801

Re: State Specifications Office
Section: 110
Proposed Specification: **1100100 Clearing and Grubbing**
Associated Specification: **9560000 Incidental Products**

Dear Mr. Holt:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Ryan Gray to move material and payment information from Index 110-200 into the specifications.

Please review and transmit your comments, if any, within two weeks (10 business days). Comments should be sent via email daniel.strickland@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at (850) 414-4130.

Sincerely,

Signature on File

Daniel Strickland, P.E.
State Specifications Engineer

DS/am
Attachment
cc: Florida Transportation Builders' Assoc.
State Construction Engineer

CLEARING AND GRUBBING
(REV 5-11-26)

ARTICLE 110-1 is deleted and the following substituted:

110-1 Description.

Clear and grub within the areas shown in the Plans. Remove and dispose of all trees, stumps, roots and other such protruding objects, buildings, structures, appurtenances, existing flexible asphalt pavement, and other facilities necessary to prepare the area for the proposed construction. Remove and dispose of all product and debris not required to be salvaged or not required to complete the construction.

Perform miscellaneous work necessary for the complete preparation of the overall project site as specified in 110-10.

Meet the following requirements:

Tree protection barrier .....Standards Plans, Index 110-100
Mailboxes* and Posts* ..... ~~USPS STD-7C~~Section 956
Grout for Plugging Wells.....FAC 62C-29.009
Non-Grout materials for Plugging Wells*.....FAC 62C-29.009

*Use products on the Department's Approved Product list (APL).

SUBARTICLE 110-10.3 is deleted and the following substituted:

110-10.3 Mailboxes: When the Contract Documents require furnishing and installing mailboxes, ~~permit each owner to remove the existing mailbox.~~ provide written notice to the delivery route's Postmaster at least 7 days before beginning work, excluding Saturdays, Sundays, and holidays. Furnish and install one mailbox at each delivery location in accordance with the Standard Plans and maintain each mailbox for the duration of the Contract. Apply box numbers in accordance with the identification specifications of the USPS Domestic Mail Manual requirements, including house numbers and street names where authorized by the Postmaster. Coordinate removal of existing mailboxes with patrons; allow patrons to remove their mailbox or leave the mailbox for removal by the Contractor. Immediately after installation of new mailboxes, notify each "Mail Delivery Patron" by Certified Mail that removal must be completed within 21 days of receipt. Otherwise, w~~W~~ork with the Local Postmaster to develop a method of temporary mail service for the period between removal and installation of the new mailboxes. ~~Install the mailboxes in accordance with the Standard Plans.~~ Dispose of removed mailboxes and supports. Existing mailboxes that are structurally and functionally sound are not required to be reused, but may be used in lieu of constructing new mailboxes when they comply with Standard Plans Index 110-200 and reuse is approved by the Engineer.

SUBARTICLE 110-11.6 is deleted and the following substituted:

110-11.6 Mailboxes: The quantity to be paid for will be the number of mailboxes per patron address acceptably furnished and installed, reused, or relocated, regardless of the number of mailboxes per support.

SUBARTICLE 110-12.6 is deleted and the following substituted:

110-12.6 Mailboxes: Price and payment will be full compensation for all work and materials ~~required~~described in this Section, including supports, hardware, ~~and numbers~~identification markings, removal and disposition of existing mailbox, and all incidentals necessary to complete the work. No payment will be made for furnishing, installing, resetting, or relocating Neighborhood Delivery and Collection Box Units (NDCBU).

CLEARING AND GRUBBING
(REV 5-11-26)

ARTICLE 110-1 is deleted and the following substituted:

110-1 Description.

Clear and grub within the areas shown in the Plans. Remove and dispose of all trees, stumps, roots and other such protruding objects, buildings, structures, appurtenances, existing flexible asphalt pavement, and other facilities necessary to prepare the area for the proposed construction. Remove and dispose of all product and debris not required to be salvaged or not required to complete the construction.

Perform miscellaneous work necessary for the complete preparation of the overall project site as specified in 110-10.

Meet the following requirements:

Tree protection barrier .....Standards Plans, Index 110-100
Mailboxes* and Posts* .....Section 956
Grout for Plugging Wells.....FAC 62C-29.009
Non-Grout materials for Plugging Wells*.....FAC 62C-29.009

*Use products on the Department's Approved Product list (APL).

SUBARTICLE 110-10.3 is deleted and the following substituted:

110-10.3 Mailboxes: When the Contract Documents require furnishing and installing mailboxes, provide written notice to the delivery route's Postmaster at least 7 days before beginning work, excluding Saturdays, Sundays, and holidays. Furnish and install one mailbox at each delivery location in accordance with the Standard Plans and maintain each mailbox for the duration of the Contract. Apply box numbers in accordance with the identification specifications of the USPS Domestic Mail Manual requirements, including house numbers and street names where authorized by the Postmaster. Coordinate removal of existing mailboxes with patrons; allow patrons to remove their mailbox or leave the mailbox for removal by the Contractor. Immediately after installation of new mailboxes, notify each "Mail Delivery Patron" by Certified Mail that removal must be completed within 21 days of receipt. Otherwise, work with the Local Postmaster to develop a method of temporary mail service for the period between removal and installation of the new mailboxes. Dispose of removed mailboxes and supports. Existing mailboxes that are structurally and functionally sound are not required to be reused, but may be used in lieu of constructing new mailboxes when they comply with Standard Plans Index 110-200 and reuse is approved by the Engineer.

SUBARTICLE 110-11.6 is deleted and the following substituted:

110-11.6 Mailboxes: The quantity to be paid for will be the number of mailboxes per patron address acceptably furnished and installed, reused, or relocated, regardless of the number of mailboxes per support.

SUBARTICLE 110-12.6 is deleted and the following substituted:

110-12.6 Mailboxes: Price and payment will be full compensation for all work and materials described in this Section, including supports, hardware, identification markings, removal and disposition of existing mailbox, and all incidentals necessary to complete the work. No payment will be made for furnishing, installing, resetting, or relocating Neighborhood Delivery and Collection Box Units (NDCBU).