

Origination Form

Specifications

Name:	Ryan Gray	Standard Specification Section:	110
Email:	ryan.gray@dot.state.fl.us	Special Provision:	
Date:	2026-05-08T15:00:19Z	Associated Specs:	956 (new)

Summary:

Move material and payment information from Index 110-200 into the Specifications. (Goes With Index 110-200 updates)

Justification:

Multiple notes in the associated Index contained specification information.

Do the changes affect other types of specifications?

Neither

List Specifications Affected:

Other Affected Documents/Offices	Contacted	Yes/No
Other Standard Plans	Ryan Gray	Yes
Florida Design Manual		No
Structures Manual		No
Basis of Estimates Manual		No
Approved Product List	Melissa Hollis	Yes
Construction Office		No
Maintenance Office		No
Materials Manual		No
Traffic Engineering Manual		No

Are changes in line with promoting and making progress on improving safety, enhancing mobility, inspiring innovation, and fostering talent; explain how?

N/A

What financial impact does the change have; project costs, pay item structure, or consultant fees?

None

What impact does the change have on production or construction schedules?

None

How does this change improve efficiency or quality?

N/A

Which FDOT offices does the change impact?

Design

What is the impact to districts with this change?

None

Does the change shift risk and to who?

N/A

Provide summary and resolution of any outstanding comments from the districts or industry.

Comments and Responses are available on the Track the Status of Revisions hyperlink located on the Specifications landing page: <https://www.fdot.gov/specifications/default.shtm>

What is the communication plan?

Through the established specification revision process (e.g., Internal and Industry Review)

What is the schedule for implementation?

The Standard Specifications eBook and Workbook are effective July 1st every year.

CLEARING AND GRUBBING (REV 5-11-26)

ARTICLE 110-1 is deleted and the following substituted:

110-1 Description.

Clear and grub within the areas shown in the Plans. Remove and dispose of all trees, stumps, roots and other such protruding objects, buildings, structures, appurtenances, existing flexible asphalt pavement, and other facilities necessary to prepare the area for the proposed construction. Remove and dispose of all product and debris not required to be salvaged or not required to complete the construction.

Perform miscellaneous work necessary for the complete preparation of the overall project site as specified in 110-10.

Meet the following requirements:

Tree protection barrierStandards Plans, Index 110-100

Mailboxes* and Posts* ~~USPS STD 7C~~ Section 956

Grout for Plugging Wells.....FAC 62C-29.009

Non-Grout materials for Plugging Wells*FAC 62C-29.009

*Use products on the Department's Approved Product list (APL).

SUBARTICLE 110-10.3 is deleted and the following substituted:

110-10.3 Mailboxes: When the Contract Documents require furnishing and installing mailboxes, ~~permit each owner to remove the existing mailbox.~~ provide written notice to the delivery route's Postmaster at least 7 days before beginning work, excluding Saturdays, Sundays, and holidays. Furnish and install one mailbox at each delivery location in accordance with the Standard Plans and maintain each mailbox for the duration of the Contract. Apply box numbers in accordance with the identification specifications of the USPS Domestic Mail Manual requirements, including house numbers and street names where authorized by the Postmaster. Coordinate removal of existing mailboxes with patrons; allow patrons to remove their mailbox or leave the mailbox for removal by the Contractor. Immediately after installation of new mailboxes, notify each "Mail Delivery Patron" by Certified Mail that removal must be completed within 21 days of receipt. Otherwise, w~~Work with the Local Postmaster to develop a method of temporary mail service for the period between removal and installation of the new mailboxes. Install the mailboxes in accordance with the Standard Plans.~~ Dispose of removed mailboxes and supports. Existing mailboxes that are structurally and functionally sound are not required to be reused, but may be used in lieu of constructing new mailboxes when they comply with Standard Plans Index 110-200 and reuse is approved by the Engineer.

SUBARTICLE 110-11.6 is deleted and the following substituted:

110-11.6 Mailboxes: The quantity to be paid for will be the number of mailboxes per patron address acceptably furnished and installed, reused, or relocated, regardless of the number of mailboxes per support.

SUBARTICLE 110-12.6 is deleted and the following substituted:

110-12.6 Mailboxes: Price and payment will be full compensation for all work and materials ~~required~~ described in this Section, including supports, ~~hardware, and~~ numbers identification markings, removal and disposition of existing mailbox, and all incidentals necessary to complete the work. No payment will be made for furnishing, installing, resetting, or relocating Neighborhood Delivery and Collection Box Units (NDCBU).