CLEARING AND GRUBBING - REMOVAL OF EXISTING BRIDGES – GENERAL. (REV 9-10-07) (FA 2-15-08) (FY 2027-28)

SUBARTICLE 110-6.1 is expanded by the following:

The debris from bridge number _____ on this Contract is designated to be delivered to _____. This agency has requested delivery of the bridge debris to _____ which is _____ miles from the project site. Assume sole responsibility for the coordination and delivery of the debris to the designated location, at no cost to the Department. Upon receipt of the debris, the receiving agency is responsible for additional costs of processing, delivery, placement and use of the material and assumes legal and permitting responsibility for the placement of the debris. Payment for delivery of the debris to the designated location is included in the cost for demolition.