**MILLING OF EXISTING ASPHALT PAVEMENT - STOCKPILING.**

**(REV 11-4-26) (FA 2-14-00) (FY 2027-28)**

ARTICLE 327-1 is deleted and the following substituted:

Remove existing asphalt concrete pavement by milling to improve the rideability and cross slope of the finished pavement, to lower the finished grade adjacent to existing curb before resurfacing, or to completely remove existing pavement.

When milling to improve rideability, the Plans will specify an average depth of cut.

For this Contract, the Department will retain ownership of _____ of the milled material. Haul and stockpile the material to remain the property of the Department at the location shown in the Plans. The Contractor will take ownership of any milled material not to be retained by the Department.

ARTICLE 327-6 is deleted and the following substituted:

**327-6 Basis of Payment.**

Price and payment will be full compensation for all work specified in this Section, including hauling and stockpiling the material at the location shown in the Plans, and hauling off or otherwise disposing of any milled material not to be retained by the Department.

Payment will be made under:

Item No.327- 70- Milling Existing Asphalt Pavement - per square yard.