MILLING OF EXISTING ASPHALT PAVEMENT - EQUIPMENT.
(REV 12-1-93) (FY 2027-28)

ARTICLE 327-2 is expanded by the following:

For this project, remove the existing asphalt from bridge decks and approach slabs using a motor grader in lieu of a milling machine.

Ensure that the removal method does not damage the underlying deck and approach slab surfaces or joints.