



Florida Department of Transportation

RON DESANTIS
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JARED W. PERDUE, P.E.
SECRETARY

August 22, 2024

Cathy Kendall
Director, Office of Technical Services
Federal Highway Administration
3500 Financial Plaza, Suite 400
Tallahassee, Florida 32312

Re: State Specifications Office
Section: 110
Proposed Specification: **1100100 Clearing and Grubbing**

Dear Ms. Kendall:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Melissa Hollis to add materials, per APL/BABA formatting.

Please review and transmit your comments, if any, within two weeks (10 business days). Comments should be sent via email daniel.strickland@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at (850) 414-4130.

Sincerely,

Signature on File

Daniel Strickland, P.E.
State Specifications Engineer

DS/dh
Attachment

cc: Florida Transportation Builders' Assoc.
State Construction Engineer

**CLEARING AND GRUBBING
(REV 5-20-24)**

ARTICLE 110-1 is deleted and the following substituted:

110-1 Description.

Clear and grub within the areas shown in the Plans. Remove and dispose of all trees, stumps, roots and other such protruding objects, buildings, structures, appurtenances, existing flexible asphalt pavement, and other facilities necessary to prepare the area for the proposed construction. Remove and dispose of all product and debris not required to be salvaged or not required to complete the construction.

Perform miscellaneous work necessary for the complete preparation of the overall project site as specified in 110-10.

Meet the following requirements:

- Tree protection barrierStandards Plans, Index 110-100
- Mailboxes* and Posts* USPS-STD-7C
- Grout for Plugging Wells.....FAC 62C-29.009
- Non-Grout materials for Plugging Wells* .FAC 62C-29.009
- *Use products on the Department’s Approved Product list (APL).

**CLEARING AND GRUBBING
(REV 5-20-24)**

ARTICLE 110-1 is deleted and the following substituted:

110-1 Description.

Clear and grub within the areas shown in the Plans. Remove and dispose of all trees, stumps, roots and other such protruding objects, buildings, structures, appurtenances, existing flexible asphalt pavement, and other facilities necessary to prepare the area for the proposed construction. Remove and dispose of all product and debris not required to be salvaged or not required to complete the construction.

Perform miscellaneous work necessary for the complete preparation of the overall project site as specified in 110-10.

Meet the following requirements:

- Tree protection barrierStandards Plans, Index 110-100
- Mailboxes* and Posts* USPS-STD-7C
- Grout for Plugging Wells.....FAC 62C-29.009
- Non-Grout materials for Plugging Wells* .FAC 62C-29.009

*Use products on the Department’s Approved Product list (APL).