Origination Form

Specifications

Name:	Oliver Chung	Specification Number:	410-1, 410-2, 410-7
Email:	oliver.chung@dot.state.fl.us	Associated Specs:	None
Date:	2024-06-17T20:27:47Z	Verified:	VERIFIED

Summary:

1. Formatting changes based on APL/BABA program. 2. Administrative update to Standard Specifications for accuracy. Current language references a "QC Managers stamp", which is incorrect. These should read "Production Facility Quality Control Stamp".

Justification:

The current specification refers to QC Managers stamp which is incorrectly worded.

Do the changes affect other types of specifications?

Neither

List Specifications Affected:

Other Affected Documents/Offices	Contacted	Yes/No
Other Standard Plans		No
Florida Design Manual		No
Structures Manual		No
Basis of Estimates Manual		No
Approved Product List		No
Construction Office		No
Maintenance Office		No
Materials Manual		No
Traffic Engineering Manual		No

Are changes in line with promoting and making progress on improving safety, enhancing mobility, inspiring innovation, and fostering talent; explain how?

No, these are formatting and administration changes.

What financial impact does the change have; project costs, pay item structure, or consultant fees?

None

What impact does the change have on production or construction schedules?

None

How does this change improve efficiency or quality?

The stamp affixed to precast elements is the Production Facility Quality Control Stamp, not the QC Manager quality control stamp. This stamp is the indicator that the structure has met all contract requirements before leaving the precast yard.

Which FDOT offices does the change impact?

District Materials and State Materials Offices

What is the impact to districts with this change?

None

Does the change shift risk and to who?

No

Provide summary and resolution of any outstanding comments from the districts or industry.

Comments and Responses are available on the Track the Status of Revisions hyperlink located on the Specifications landing page: https://www.fdot.gov/programmanagement/Specs.shtm

What is the communication plan?

Through the established specification revision process (e.g., Internal and Industry Review)

What is the schedule for implementation?

The Standard Specifications eBook and Workbook are effective July 1st every year.

PRECAST CONCRETE BOX CULVERT (REV 6-17-24)

ARTICLE 410-1 is deleted and the following substituted:

410-1 Description.

Provide precast four-sided concrete box culverts as an alternative to the structure shown in the Contract Documents. Only monolithic segments, or two-piece segments with three-sided bottom sections and a simple support top slab section, are permitted. Two-piece segments are limited to installations with a minimum of two feet fill height above the top slab.

Construct headwalls, wingwalls and other special features using cast-in-place concrete. Precast wingwalls, cut-off walls or headwalls are not permitted unless otherwise noted in the Contract Documents.

Meet the requirements in 449-1.

ARTICLE 410-2 is deleted and the following substituted:

410-2 Materials.

Ensure that the materials used for the construction of precast box culverts have certification statements from each source, showing that they meet the applicable requirements of the following:

Portland Cement Concrete*	Section 346
Reinforcing for Concrete*	Section 415
Precast Concrete Drainage Products*	Section 449
Wire for Site Cage Machines*	Section 931
Coarse Aggregate*.**	Section 901
Fine Aggregate*.**	
Curing Materials for Concrete*	
Materials For Concrete Repair***	Section 930
Non-Shrink Grout****	Section 934
Liner Repair Systems*	Section 948
Joint Materials*ASTM C443	, ASTM C877
0	r ASTM C990
Geotextile Fabrics*	Section 985

^{*} The gradation requirements of aggregates are not applicable when using dry-cast concrete.

^{**} Use products and producers listed on the Department's Approved Product List (APL).

^{**} The gradation requirements of aggregates are not applicable when using dry-cast concrete.

410-7 Handling, Storage, and Shipping.

Handle, store, and ship precast box culverts in a manner that prevents chipping, cracks, fractures, and excessive bending stress. Do not ship precast box culverts before the concrete attains the required 28-day strength.

The manufacturer is permitted to verify the shipping strength test, before 28 days, by testing compressive strength cylinders that are cured under the conditions similar to the product or by testing temperature match cured cylinders. The manufacturer may use the maturity method, ASTM C 1074, pulse velocity method in accordance with ASTM C 597, or any other approved nondestructive test method to estimate the strength of concrete for determining form removal and handling strengths or before verification of shipping strength by test cylinders.

Curing temperature and cycle must be monitored on a minimum of one box culvert curing cell from each day of production when nondestructive test methods or temperature match cured cylinders are used to determine concrete strengths.

The shipping strength test is the average compressive strength of two test cylinders. Do not ship any products until the QC Manager's stamp-Production Facility Quality Control Stamp is affixed to the product.

SUBARTICLE 410-11.1 is deleted and the following substituted:

410-11.1 General: Make field joints for precast concrete box culvert sections with either profile rubber gaskets or preformed joint sealants, unless otherwise detailed in the Plans or approved shop drawings. Joint openings at the outside face must not exceed 1-1/2 inches in the assembled position at any location along the joint perimeter. Ensure a minimum 50% overlap of the joint tongue and groove around the entire perimeter of the box in the assembled position.

Completely wrap the outside of each joint with Type D-3 geotextile filter fabric as specified in Section 514985. Provide fabric with a minimum width of 2 feet and a length sufficient to ensure a minimum overlap of 24 inches. The filter fabric must extend a minimum of 12 inches beyond each side of the joint. Secure the fabric tightly against the box culvert sections with metal or plastic strapping. Other methods which will hold the fabric securely against the wall of the culvert until the backfill is placed and compacted, may be used when approved by the Engineer. When specified in the Plans, secure the joint by a suitable device capable of holding the sections to line and grade as well as fully home. Remove these devices and repair locations as necessary if intrusive into the concrete after placing and compacting sufficient backfill to secure the sections.