Origination Form

Specifications

Name:	John Shoucair	Specification Number:	911-1, 911-2.6, 911-2.7, 911-3.1, 911-3.2, 911-3.3, 911-3.4
Email:	john.shoucair@dot.state.fl.us	Associated Specs:	285
Date:	2024-06-20T19:37:53Z	Verified:	VERIFIED

Summary:

The main change is the addition of "Calcarenite" rock as an approved base material.

Justification:

Addition of "Calcarenite" rock as an approved base material.

Do the changes affect other types of specifications?

Neither

List Specifications Affected:

Other Affected Documents/Offices	Contacted	Yes/No
Other Standard Plans		No
Florida Design Manual	Mary Jane Hayden	Yes
Structures Manual		No
Basis of Estimates Manual		No
Approved Product List		No
Construction Office		No
Maintenance Office		No
Materials Manual		No
Traffic Engineering Manual		No

Are changes in line with promoting and making progress on improving safety, enhancing mobility, inspiring innovation, and fostering talent; explain how?

The change allows approval of a new mine source with new inventory of reserves. It will likely be approved as a new source for friction course.

What financial impact does the change have; project costs, pay item structure, or consultant fees?

There are several new Department projects immediately adjacent to the mine. The short haul distance will reduce aggregate costs.

What impact does the change have on production or construction schedules?

The proximity to several new Department projects will shorten construction time.

How does this change improve efficiency or quality?

In addition to items 3 and 4, the Limerock Bearing Ratio of this materials ranges from 150 to 180 and represents high quality.

Which FDOT offices does the change impact?

Materials and Construction.

What is the impact to districts with this change?

Addition of a new mine for District 1 manpower inspection requirements.

Does the change shift risk and to who?

Risk is neutral.

Provide summary and resolution of any outstanding comments from the districts or industry.

Comments and Responses are available on the Track the Status of Revisions hyperlink located on the Specifications landing page: https://www.fdot.gov/programmanagement/Specs.shtm

What is the communication plan?

Through the established specification revision process (e.g., Internal and Industry Review)

What is the schedule for implementation?

The Standard Specifications eBook and Workbook are effective July 1st every year.

BASE AND STABILIZED BASE MATERIALS (REV 6-20-24)

ARTICLE 911-1 is deleted and the following substituted:

911-1 Description.

This Section governs materials to be used in the construction of base and subgrade stabilization including limerock, shell, shell-rock, cemented coquina shell, <u>calcarenite</u>, and recycled concrete aggregate (RCA).

ARTICLE 911-2 is deleted and the following substituted:

911-2 Materials.

911-2.1 General:

911-2.1.1 Approval of Material: Approval of mineral aggregate sources shall be in accordance with 6-2.3.

- 911-2.1.2 Deleterious Substances: Materials shall not contain deleterious substances that would result in: prevention of the bituminous prime coat from adhering to the base course; a detriment to the finishing, strength, or performance of the base; or a surface which is susceptible to distortion under construction traffic. Such substances include, but are not limited to: cherty or other extremely hard pieces, lumps, balls or pockets of sand or clay size material, organic matter, loose sand, loose, free shells, corals or skeletal remain of other marine invertebrates retained on the No. 4 sieve, or water sensitive clay minerals.
- **911-2.2 Limerock Composition:** Limerock material shall consist of unconsolidated or partly consolidated limestone of marine origin.
- 911-2.3 Shell Material: Composition: Shell materials shall consist of naturally occurring deposits formed essentially of broken mollusk shell, corals and the skeletal remains of other marine invertebrates. Live or steamed shell, or man-made deposits as a by-product of the shellfish industry will not be permitted.
- 911-2.3.1 Bank Run Shell: Shell materials meeting the requirements of this Section which are presently found as "dry land" deposits.
- 911-2.3.2 Dredged Shell: Shell materials meeting the requirements of this Section which are dredged from ocean, bay or lake deposits.
- 911-2.4 Shell-Rock Material Composition: Shell-rock materials shall consist of naturally occurring heterogeneous deposits of limestone with interbedded layers or lenses of loose and cemented shell, to include cemented sands (calcitic sandstone). This material shall be mined and processed in a manner that will result in a reasonably homogenous finished product.
- 911-2.5 Cemented Coquina Shell Material Composition: Cemented coquina shell materials to be used as cemented coquina base or stabilized base, shall be defined as naturally occurring deposits formed essentially of broken mollusk shell, corals and the skeletal remains of other marine invertebrates, which are presently found as "dry land" deposits and which have been cemented together by carbonates or other natural cementing agents.

- 911-2.6 Calcarenite Composition: Calcarenite material shall consist of calcareous clastic sedimentary rock, formed by compaction and cementation of carbonate clasts of size between 0.06 and 2 mm. It also contains a calcareous cementing material that binds the sand grains together.
- 911-2. 6-7 Recycled Concrete Aggregate (RCA) Composition: RCA shall consist of concrete material derived from the crushing of hard portland cement concrete. In addition to the deleterious materials noted in 911-2.1.2, RCA shall be asbestos free. The following limits shall not be exceeded:

Bituminous Concrete	1% by weight
Bricks	1% by weight
Glass and Ceramics	1% by weight
Wood and other organic substances	0.1% by weight
Reinforcing steel and welded wire fabric	0.1% by weight
Plaster and gypsum board	0.1% by weight

ARTICLE 911-3 is deleted and the following substituted:

911-3 Material Requirements.

911-3.1 Limerock Bearing Ratio (LBR): Materials shall meet the requirements in Table 911-1 in accordance with FM 5-515:

Table 911-1 Limerock Bearing Ratio (LBR)			
Material	Requirement		
Limerock			
Shell	Assessed Benefits and LOT 100 minimum		
Shell-Rock	Average Results per LOT - 100, minimum Individual Results - 90, minimum		
Cemented Coquina Shell	individual Results - 90, minimum		
Calcarenite			
RCA Individual Results - 150, minimum			

911-3.2 Liquid Limit and Plasticity: Materials shall meet the requirements in Table 911-2 in accordance with AASHTO T 89 and AASHTO T 90:

Table 911-2				
Liquid Limit and Plastic Properties				
Material		Liquid Limit	Plastic Properties	
Limerock	Base	Not to exceed 35	Non-Plastic (NP)	
Limerock	Stabilized Base		Plasticity not to exceed 10	
Shell			ND	
Shell-Rock		-	NP	
Cemented Coquina Shell		-	NP	
<u>Calcarenite</u>		<u>-</u>	<u>NP</u>	
RCA		-	NP	

911-3.3 Carbonates: Materials shall meet the carbonate requirements in Table 911-3 in accordance with FM 5-514:

Table 911-3			
Percentage of Carbonates (Calcium and Magnesium)			
Material	Requirement		
Limerock	minimum - 70%		
Shell	minimum - 50%		
Shell-Rock	minimum - 50%		
Cemented Coquina Shell	minimum - 50%		
<u>Calcarenite</u>	<u>minimum - 45%</u>		
RCA	Not Applicable		

911-3.4 Gradation and Size Requirements: Materials shall meet the gradation and size requirements in Table 911-4 in accordance with FM 1-T27 and FM 1-T11:

		Table 911-4 ⁽¹⁾		
		Gradation Requirements		
Material		Requirement		
Limerock	Base	Passing 3-1/2 inch sieve - 97%, minimum		
		At least 97% shall pass a 3-1/2 inch sieve ⁽²⁾		
	Stabilized Base	Passing 3-1/2 inch sieve - 97%, minimum At least 97% shall pass a 1-1/2 inch sieve (2)		
		Passing 3-1/2 inch sieve - 97%, minimum		
	Dredged shell	Passing No. 4 sieve - 50%, maximum		
Shell		Passing No. 200 sieve - maximum 7.5% (washed)		
SHCH		Passing 3-1/2 inch sieve - 97%, minimum		
	Bank-run shell	Passing No. 4 sieve - 80%, maximum		
		Passing No. 200 sieve - 20%, maximum (washed)		
Shell-Rock		Passing 3-1/2 inch sieve - 97%, minimum		
		Passing No. 4 sieve - 70%, maximum		
Cemented Coquina Shell		Passing No. 200 sieve - 20%, maximum (washed)		
Calcarenite		Passing 3-1/2 inch sieve - 97%, minimum ⁽²⁾		
		Sieve Size	Percent by Weight Passing	
		2 inch	100	
		3/4 inch	65 to 95	
D.C.A		3/8 inch	40 to 85	
RCA		No. 4	25 to 65	
		No. 10	20 to 50	
		No. 50	5 to 30	
		No. 200	0 to 10	
	num dimension shall not exc			
2) The materi	ıal shall be well graded dowi	n to dust. The fine material shall consis	st entirely of dust of fracture.	