

FDOT Transportation Innovation Initiative: FRP-RC/PC – Design Innovation



Fast Facts:

Glass
Fiber Reinforced
Polymer Bars
&
Carbon Fiber
Reinforced
Polymer/HSS
Strands



Project Location:

FDOT District Four
Palm Beach County
North Palm Beach, Florida

Agency/Owner:

Florida Department of Transportation

URL:

<http://www.fdot.gov/structures/innovation/FRP.shtm>

Project Name:

SR 5 (US 1) over Earman River
Bridge No. 930564
FPID: 442891-1 (T4714)

Project Description:


Bridge replacement with 3-span FSB
superstructure and pile bents.

Project Purpose & Need:

Following the failure of the exterior slab unit in
Span 2 (*see image below*) and subsequent



inspection, the structure was
classified as structurally
deficient and identified for
replacement. Corrosion and
complete section loss of the
transverse post-tensioning
led to the failure. The
proposed typical section
maintains 3 lanes in each
direction with a large 11'-4"
sidewalk on each side.



What was unique about this project? First full bridge replacement in District IV to use FSBs (3,477 LF) with CFRP/HSSS strands and Basalt/Glass FRP/SS auxiliary reinforcement. The typical FSB intermediate bent detail with an expansion joint is modified to eliminate the joint (link-slab). Basalt/Glass FRP reinforcement is used in the bent caps and C.I.P topping (148,000 LF).

Describe Traditional Approach: Traditional approach includes addition of flyash, blast furnace slag, silica fume and other corrosion inhibitors into cement rich concrete mixes to protect carbon-steel prestressing strands and reinforcing with limited long-term success, especially in the presence of concrete cracking.

Describe New Approach: In lieu of carbon-steel prestressing strands and mild reinforcing, the FSBs will utilize CFRP or HSSS prestressing strands and Basalt/Glass FRP or SS reinforcing. The C.I.P. topping and pile bent caps will utilize Basalt/Glass FRP bars with reduced concrete cover. Highly reactive pozzolans are still used with HSSS prestressing strands.

Top Innovations Employed: Utilization of CFRP/HSSS prestressing strands and Basalt/Glass FRP bars within the splash zone/marine environment.

Primary Benefits Realized/Expected: Longer service life of the bridge without major maintenance.

Project Start/Completion Date: Jan. 2025 – Dec. 2026 (Bid Solicitation Notice [T4717](#))

Construction Estimate: \$16,000,000

Affiliations: PE Consultant (Roadway): American Consulting Professionals, LLC
 Construction Contractor: TBA
 Construction Engineering Inspection: Pinnacle Consulting Enterprises, Inc.

Project Contact: Engineer of Record (Bridge): Joseph Donegan, P.E.
 FDOT District Four
Joseph.Donegan@dot.state.fl.us
 FDOT Project Manager: Bing Wang, P.E.
 FDOT District Four
Bing.Wang@dot.state.fl.us
 FDOT State Materials Office: Alexander Lewis
 FDOT Composite Materials Specialist
alexander.lewis@dot.state.fl.us