


# FDOT Transportation Innovation Initiative: FRP – Design Innovation



**Fast  
Facts:  
Glass  
Fiber-  
Reinforced  
Polymer**



**Project Location:** FDOT District Two  
Duval County, FL

**Agency:** Florida Department of Transportation

**URL:** <http://www.fdot.gov/structures/innovation/FRP.shtm>

**Project Name:** SR105 (A1A) over Myrtle Creek  
Bridge No. 720857  
FPID: 434042-1-52-01

**Project Description:** Bridge replacement with 3-span prestressed slab-beam bridge.


**Project Purpose & Need:** Bridge replacement and widening in estuary using GFRP-RC link-slab on Florida Slab-Beams (FSB)

**Overall Budget/Cost Estimate:** \$3,500,000

**What was unique about this project?** First GFRP-RC link-slab for FDOT vehicular bridge, along with adjacent bridge SR 105 (A1A) over Simpson Creek

**Describe Traditional Approach:** Traditional approach includes an open joint at the end of each FSB span. For slab-on-girder bridges nominal reinforcing using #5's at 6-inch spacing and a transverse tooled or early age saw cut joint used to control crack propagation above the intermediate piers. This was found not to be effective with previous prestressed slab-beam units (PSU), presumably due to the high degree of shrinkage restraint.

**Describe New Approach:** Utilization of lower modulus GFRP bars, with appropriate debonding limits above the prestressed slab interface to improve performance. If cracks do develop, the concern for corrosion is eliminated by the use of non-corrodible FRP reinforcing.



**Top Innovations Employed:** Utilization of GFRP bars and adoption of link-slabs to provide lateral load distribution and eliminate intermediate support expansion joints, without significantly restricting superstructure rotation at the support that could otherwise create secondary forces and cracking stresses.

**Primary Benefits Realized/Expected:** Longer service life of the bridge deck, elimination of expansion joint maintenance, and better transfer of lateral loads due to deck continuity.

**Project Start Date/Substantial Completion Date:** Spring 2021 – TBA

|                         |                                      |                              |
|-------------------------|--------------------------------------|------------------------------|
| <b>Affiliations:</b>    | PE Consultant:                       | STV Inc.                     |
|                         | Construction Contractor:             | TBA.                         |
|                         | Construction Engineering Inspection: | TBA                          |
| <b>Project Contact:</b> | Engineer of Record:                  | Terry Hall, P.E.<br>STV Inc. |



|                       |   |
|-----------------------|---|
| FDOT Project Manager: | Craig Teal, P.E.<br>FDOT District Two<br><a href="mailto:Craig.Teal@dot.state.fl.us">Craig.Teal@dot.state.fl.us</a> |
|-----------------------|---|