

# Joint Design Optimization for Accelerated Construction of Slab Beam Bridges

F. D. Chitty<sup>1</sup>, C. J. Freeman<sup>2</sup>, and D. B. Garber<sup>3</sup>

<sup>1</sup> Graduate Research Assistant, Dept. of Civil and Environmental Engineering, Florida International University, 10555 West Flagler Street, Miami, FL 33174, (corresponding author).

Email: [fchit001@fiu.edu](mailto:fchit001@fiu.edu)

<sup>2</sup> Structures Research Engineer, Structures Research Center, Florida Department of Transportation, 2007 E. Paul Dirac Dr. Tallahassee, FL 32310. Email:

[christina.freeman@dot.state.fl.us](mailto:christina.freeman@dot.state.fl.us)

<sup>3</sup> Assistant Professor, Dept. of Civil and Environmental Engineering, Florida International University, 10555 West Flagler Street, Miami, FL 33174. Email: [dgarber@fiu.edu](mailto:dgarber@fiu.edu)

## ABSTRACT

The Florida Slab Beam (FSB) has been developed by the Florida Department of Transportation (FDOT) to be used for short-span bridges (less than about 19.8 m [65 ft.] long). The FSB system consists of shallow precast, prestressed concrete inverted-tee beams that are placed adjacent to each other and then involve reinforcement and concrete being placed in the inner joints and deck all in one single cast. Ultra-high-performance concrete (UHPC) is becoming more widely used in bridge construction applications due to its remarkable structural performance. Many departments of transportation have tested and deployed the use of UHPC in bridges around the US. Most of these applications have been to connect precast members (e.g. slabs to beams and slabs, adjacent beams, caps to columns, etc.). A modified FSB design is desired to eliminate the cast-in-place (CIP) deck and allow for UHPC to be used in the joint region, which will allow for accelerated

24 construction and decrease the impact of construction on traffic. Different joint details and cross-  
25 section geometries were analyzed and experimentally evaluated to determine feasible joint details  
26 with UHPC for slab beam bridges used in accelerated construction. Results from numerical  
27 modeling, strength, and fatigue experimental testing of the transverse joint performance of four  
28 different UHPC joints in two different depth slab beam bridges are presented. The straight-side  
29 and shear-key UHPC joint details were found to behave similar to or better than the current FSB  
30 joint detail.

31 **CE Database Keywords:**

32 Ultra-high performance concrete, accelerated bridge construction, prefabricated elements and  
33 systems, non-linear finite element analysis, slab beam bridge

34 **INTRODUCTION**

35 There are over 600,000 bridges in the US with about 40 percent of them at least 50 years old and  
36 about nine percent of them being structurally deficient (American Society of Civil Engineers  
37 (ASCE), 2017). In Florida, the majority of the structurally deficient or functionally obsolete  
38 bridges are short-span bridges, including slab beam systems with deficient load transfer capacity  
39 due to strength decay in their joints; approximately 90 percent of these bridges are less than 18 m  
40 (60 ft.) long (Nolan, Freeman, Kelley, & Rossini, 2018). There has been a need to develop  
41 solutions for rapidly replacing, repairing or retrofitting these structures while minimizing the  
42 impact to traffic during construction. Accelerated bridge construction (ABC) techniques,  
43 specifically prefabricated bridge elements and systems (PBES), can provide such a solution. Slab  
44 beam superstructures, one type of prefabricated element, can be used with ultra-high performance  
45 concrete (UHPC) to create a resilient superstructure system that can offer accelerated construction  
46 with enhanced serviceability performance. The development of a joint detail for such a slab beam

47 system that enhances load transfer capacity through numerical modeling and experimental testing  
48 of joints in flexure is summarized in this paper.

### 49 **Slab Beam Superstructures**


50 Slab beams have been used in bridge superstructure construction since prestressing began in the  
51 United States in the 1950s. Slab beam superstructures are characterized by having shallow depth,  
52 prestressed, precast concrete, and are placed side-by-side with a concrete joint cast in between  
53 them. Due to their shallow depths, the beam section is typically suitable for bridge spans less than  
54 22.9 m (75 ft.) in length. Texas (Texas Department of Transportation (TxDOT), 2018), Minnesota  
55 (Federal Highway Administration (FHWA), 2015), Virginia (Menkulasi, Mercer, Wollmann, &  
56 Cousins, 2012), and Florida departments of transportation have used different slab beam  
57 configurations with different longitudinal joint and transverse tie mechanisms to ensure  
58 appropriate load transfer between adjacent members. The Florida Department of Transportation  
59 (FDOT) bridge inventory has developed six iterations of slab beam bridges that have been built  
60 since the 1950s (Nolan et al., 2018). The first of these slab beam bridges was the prestressed  
61 rectangular slab unit, shown in Fig. 1 (a). This system did not have a cast-in-place (CIP) concrete  
62 deck and was connected through a longitudinal, 254 mm (10 in.) wide, concrete closure pour. The  
63 width of the joint was dependent on the required development length of the transverse steel  
64 projecting in the closure pour. In 1958, the system was modified to enhance its capacity by adding  
65 a 102-mm (4-in.) CIP reinforced concrete deck that was cast with the joint as shown in Fig. 1 (b).  
66 The joint was modified by extending the bottom concrete ledges such that forming underneath the  
67 superstructure was not required and transverse post-tensioned tie bars in sleeves were used as the  
68 transverse joint reinforcement. Later in the 1950s, a lighter version of the slab unit called Sonovoid  
69 (voided slab) began to be used, shown in Fig. 1 (c). Sonovoids have a reduced weight due to

70 cylindrical voids running along the length of the beam and an asphalt layer in place of the 102-mm  
71 (4-in.) thick CIP deck; the asphalt overlay was used to accommodate differential camber between  
72 adjacent beams. The overall joint geometry was decreased to small shear keys filled with grout.  
73 The same transverse post-tensioned tie bar detail was used to provide for the force transfer between  
74 adjacent beams. These cross-sections developed by FDOT regional offices were used for the next  
75 few decades. The next major development in the FDOT slab beam systems was the Prestressed  
76 Slab Unit (PSU), shown in Fig. 1 (d), which first appeared in 2008 and was standardized in 2009.  
77 The PSU was simpler to construct in the field as it eliminated the need for transverse tie bars. The  
78 load transfer between adjacent members relied on a grouted shear key and a 153-mm (6-in.) thick  
79 CIP reinforced concrete deck that acted in composite action with the slab beams.

80 There have been some issues observed with existing slab beam systems in Florida (FDOT, 2013;  
81 Nolan et al., 2018) shown in Fig. 1 (a) – (d). The transverse capacity of the joint has decayed  
82 rapidly during service loading in some deployed bridges, indicated by longitudinal cracking at the  
83 joints along the length of the beams. This behavior would suggest that the slab beam superstructure  
84 system is not behaving as a composite unit, but rather load is being primarily carried by the beam  
85 on which it is directly applied.

86 Poor performance of these systems led FDOT to the development of an alternate system in 2005,  
87 the Florida Slab Beam (FSB), shown in Fig. 1 (e). The FSB was developed for use on low volume,  
88 short-span bridges (less than about 19.8 m [65 ft.] long). It consists of shallow precast, prestressed  
89 concrete inverted-tee beams that are placed side by side, allowing the bottom lip to serve as a  
90 bottom form for the CIP joint and deck. A steel reinforcement cage is placed in the joint region  
91 with an additional steel reinforcement mat for the top deck. A monolithic concrete joint and slab  
92 are cast after all the reinforcement is placed.

93 The section shares some characteristics with the Precast Composite Slab Span System (PCSSS)  
 94 developed by Minnesota in 2005 (Bell, French, & Shield, 2006; French et al., 2011; Smith,  
 95 Eriksson, Shield, & French, 2008), shown in Fig. 1 (f), which was the first shallow inverted-T  
 96 prestressed concrete system with straight web sides and bottom ledges that served as stay-in-place  
 97 formwork. The main difference between the FSB and the PCSSS system is that the PCSSS has  
 98 projecting rebar hooks that extend transversely through the joint creating a lapped splice, while the  
 99 projecting rebar hooks in the FSB do not extend beyond the edge of the bottom lip. The detail in  
 100 the FSB was intended to improve constructability by eliminating the potential of projecting rebars  
 101 from adjacent members interfering with each other.



102  
 103 **Fig. 1:** Slab beam system evolution in Florida: (a) prestressed rectangular slab unit (1955), (b)  
 104 prestressed keyed slab unit (1958), (c) prestressed voided slab units – Sonovoid (1958), (d)  
 105 prestressed slab unit – PSU (2008), (e) Florida Slab Beam – FSB (2015), based on (Goldsberry,  
 106 2015), and (f) precast composite slab span system – PCSS (2005).

107 After the PCSSS development, MnDOT implemented the system in two pilot bridge projects with  
108 one of the bridges instrumented and monitored to investigate the in-service performance and  
109 possible reflective cracks on the CIP deck (Smith et al., 2008). It was found that cracking initiated  
110 in CIP deck regions immediately above the vertical sides of the beam webs over the ledged joints,  
111 and the researchers determined that these cracks resulted from restrained concrete shrinkage and  
112 environmental effects rather than traffic loads (French et al., 2011; Smith et al., 2008). Ten  
113 additional bridges were constructed between 2005 and 2011, giving a total of 12 bridges  
114 constructed in Minnesota with a version of the PCSSS system. Five of these bridges were inspected  
115 in 2011 to determine their performance (Halverson, French, & Shield, 2012). Halverson et al.  
116 (2012) found there to be extensive cracking and efflorescence located on the bottom of the  
117 superstructure near joints in the inspected bridges. An optimized inverted T-beam was later  
118 proposed by researchers from Virginia with revised web section that included tapered sides. This  
119 solution was shown to decrease stress concentrations that could occur in abrupt geometry changes  
120 in the slab beam web (Menkulasi et al., 2012; Menkulasi, Cousins, & Wollmann, 2018), but  
121 researchers still found that stresses from temperature and time effects were still significant  
122 (Menkulasi et al., 2018).

### 123 **Research Motivation, Objective, and Significance**

124 The research discussed in this paper had two primary motivations: (1) the poor performance of  
125 previously used slab beam systems for short-span bridges evidenced by reflective cracking along  
126 the joint line in in-service bridges and (2) the desire to create a short-span bridge solution for  
127 accelerated construction. The primary objective of the research discussed in this paper was to  
128 develop a cross section for short-span bridges (less than 22.9 m [75 ft.] in length) and a joint design  
129 utilizing UHPC with satisfactory strength and fatigue performance, which allows for accelerated

130 construction of the superstructure. UHPC was selected as the joint material for this research as it  
131 has been previously used in accelerated bridge construction applications to connect other precast  
132 members (e.g. full-depth precast deck panels, adjacent box beams). The research discussed in this  
133 paper is significant as it addresses the future construction of short-span bridges, which make up  
134 the vast majority of structurally deficient and functionally obsolete bridges.

### 135 **Previously Investigated Joint Details with UHPC**

136 Ultra-High-Performance Concrete (UHPC) is becoming more widely used due to its high  
137 compressive and tensile strength, improved long-term durability, low permeability, and high  
138 flowability. Also, UHPC has been used for constructing prefabricated bridge elements and  
139 overlays, but its primary application to date has been for the joints between prefabricated elements  
140 (Russell & Graybeal, 2013). The high tensile strength of UHPC decreases the required joint size  
141 and improves the joint durability between prefabricated elements; UHPC has been shown to  
142 provide a stronger connection than the prefabricated members themselves (Graybeal, 2010).

143 There have been several research efforts that have investigated UHPC joints between full-depth  
144 precast concrete deck panels (Aaleti & Sritharan, 2014; Graybeal, 2014b) and adjacent box beams  
145 (Yuan, Graybeal, & Zmetra, 2018). A study conducted by Aaleti and Sritharan (Aaleti & Sritharan,  
146 2014) determined the four most popular joint geometries used in panel-to-panel connections with  
147 different steel rebar configurations: lap spliced bars, headed bars, non-contact lap spliced bars, and  
148 hooked bars. A UHPC joint geometry with non-contact, lap spliced transverse rebar was later  
149 developed to connect adjacent box bridge superstructures (Yuan et al., 2018); the details of this  
150 joint were based on previously discussed joint geometries.

151 Guidelines for UHPC field-cast joint construction were developed based on the extensive research  
152 conducted by the Federal Highway Administration (FHWA) (Graybeal, 2014a). These guidelines

153 were developed based on findings from the previously mentioned research on joint connections,  
 154 additional reinforcement pull out and development testing (Yuan & Graybeal, 2014), and UHPC  
 155 material testing (Haber, De la Varga, Graybeal, Nakashoji, & El-Helou, 2018).

156 **DEVELOPMENT OF UHPC JOINT GEOMETRY AND REINFORCEMENT DETAIL**

157 The design embedment lengths, cover, lap splice length, and spacing between non-contact lap  
 158 spliced bars in UHPC were chosen as recommended by Graybeal (Graybeal, 2014a) as a starting  
 159 point. The recommended and provided values for the #16 (#5) joint reinforcement ( $d_b = 15.9$  mm  
 160 [0.625 in.]) are shown in Table 1; the joint regions proposed for testing use #16 (#5) rebar as the  
 161 primary joint reinforcement. These design recommendations are valid for a UHPC mix with 2-  
 162 percent (by volume) steel fiber reinforcement and a compressive strength of at least 96.46 MPa  
 163 (14 ksi). This value allows for accelerated construction applications, as a typical UHPC mix can  
 164 reach above 96.46 MPa (14 ksi) within the first few days after casting (Graybeal, 2006).

165 **Table 1.** *Design values for UHPC connections (based on (Graybeal, 2014a))*

<b>Parameter</b>	<b>Formula</b>	<b>Value</b>	<b>Provided</b>
<b>Embedment Length</b>	$l_d = 8d_b$	$8 * 15.9 \text{ mm} = 127.2 \text{ mm}$	127.2 mm or 161.9 mm
<b>Cover</b>	$\geq 3d_b$	$3 * 15.9 \text{ mm} = 47.7 \text{ mm}$	47.6 mm
<b>Lap splice length</b>	$l_s = 0.75l_d$	$0.75 * 127.2" = 95.4 \text{ mm}$	101.6 mm or 133.3 mm
<b>Max. clear spacing</b>	$l_s$	95.2 mm	60.3 mm


166 Note:  $l_d =$  embedment length;  $l_s =$  lap splice length; 1 in. = 25.4 mm

167 Two categories of joint geometries were developed for investigation in this project: (1) straight  
 168 joint sides with no shear key and (2) traditional shear key shape. The width of the joints with  
 169 straight sides and no shear key was based on the required embedment length and splice length of  
 170 the joint reinforcement. As UHPC allows for a shorter embedment and development lengths, only  
 171 a 153-mm (6-in.) wide joint was required, resulting in two joint geometries called FDOT 1 (F1)



172 and FDOT 2 (F2), as shown in Fig. 2 (a) and (b). A bottom lip was still provided in these joints to  
173 allow for the joint to be constructed without bottom forming of the joint. Two different thickness  
174 bottom lips were provided: a 102-mm (4-in.) lip with reinforcement extending into it in joint F1,  
175 and a 51-mm (2-in.) lip without reinforcement extending into the lip in joint F2, shown in Fig. 2  
176 (a) and (b), respectively. The thinner bottom lip dimension allowed for the joint reinforcement to  
177 be moved further down in the section but did not allow for reinforcement to be extended into the  
178 lip.

179 One traditional shear key detail was chosen to allow for a larger embedment length of the joint  
180 reinforcement while keeping a similar joint area. This detail was based on a previously  
181 recommended detail for the connection between adjacent box beams (Graybeal, 2014a; Yuan et  
182 al., 2018), and it is called Alternate 1 (A1) as shown in Fig. 2 (c). The splice length of the joint  
183 reinforcement was the same as joint F1 and F2 previously described. The depth of the joint  
184 reinforcement in joint A1 (162 mm [6.4 in.]) was larger than that of joint F1 (158 mm [6.2 in.]). A  
185 second shear key detail, shown in Fig. 2 (d) and called Alternate 2 (A2), was developed to: (1)  
186 lower the height of the joint reinforcement, (2) increase the splice length of the reinforcement, and  
187 (3) strengthen the top flange portion of the joint.



188

189 **Fig. 2:** Details for joint: (a) FDOT 1 (F1), (b) FDOT 2 (F2), (c) Alternate 1 (A1), and (d)

190 Alternate 2 (A2). (units: mm, 1 mm = 0.0394 in)

191 The performance of the proposed UHPC joint specimens was compared to the performance of a  
 192 control specimen, called FSB, which had a joint designed using the original FSB construction  
 193 detail (FDOT, 2016b). This detail requires #16 (#5) hooked joint reinforcement with a bend  
 194 diameter of 64 mm (2.5 in.) extending 127 mm (5 in.) from the precast beams with a height  
 195 measured from the base of the member of 165 mm (6.5 in.), as shown in Fig. 1 (e). The  
 196 reinforcement installed in the field includes hooped bars in the joint, longitudinal joint

197 reinforcement along the length of the beam, and deck reinforcement all of which are #16 (#5) bars.  
198 The joint and CIP deck are then cast at the same time.

199 These joint details were evaluated through the following numerical and experimental  
200 investigations using 305-mm (12-in.) and 457-mm (18-in.) deep specimens with reinforcement  
201 details similar to those recommended by the original FSB construction guidance (FDOT, 2016b).

## 202 **NUMERICAL INVESTIGATION**

203 Finite element analysis (FEA) was first used to determine the failure mechanism of the proposed  
204 joint geometries. FEA served to initially evaluate the performance of the joints and to determine  
205 the geometry of the specimens (length, width, and depth) to ensure a flexural failure mechanism  
206 with expected failure loads within the testing frame capabilities.


### 207 **Numerical Methods**

208 The response of all the laboratory specimens were first estimated using a commercial non-linear  
209 FEA package named ATENA® specially designed for modeling reinforced concrete elements in  
210 the elastic, post-cracking, and ultimate capacity ranges. The software uses the Fracture-Plastic  
211 Constitutive Model: tensile (fracturing) and compressive (plastic) behavior (V. Cervenka, Jendele,  
212 & Cervenka, 2016), which is suitable to simulate concrete cracking, crushing under high  
213 confinement, and crack closure due to crushing in other material directions.

### 214 **Specimen Geometry**

215 Numerical models were developed for eight joint geometries to be tested in two groups: (1) 457-  
216 mm (18-in.) deep beams (Control FSB, F1, F2, and A1), and (2) 305-mm (12-in.) deep beams (F1,  
217 F2, A1, and A2), as shown in Fig. 3. These joint specimens consisted of two beams with the same  
218 joint geometry placed side by side and loaded to study the transverse flexural capacity of the joints.  
219 There are three main slab-beam depths in the current FSB Specifications (FDOT, 2016b). The

220 control FSB specimen was designed using a 305-mm (12-in.) deep standard FSB section with a  
 221 1,520-mm (60-in.) wide (FSB 12x60) and a 152-mm (6-in.) deep CIP deck, giving an overall  
 222 thickness of 457 mm (18 in.). The smallest and largest slab beam depths in the current FSB  
 223 Specification (305 mm and 457 mm [12 in. and 18 in.]) were chosen for the investigation of the  
 224 other UHPC joint specimens without CIP decks.



225  
 226 **Fig. 3:** Specimen details for analytical and experimental program. (units: mm, 1 mm =0.0394 in)  
 227 The FSB control served as a comparison for the 457-mm (18-in.) deep UHPC joint specimens.  
 228 The overall thickness of the section is designated as the first number in the specimen name (e.g.,  
 229 12F1 is a 12-inch thick specimen with joint F1).

230 Ten total 15-mm (0.6-in.) diameter prestressing strands were located parallel to the joint in the  
 231 beam section. Four strands were spread out across the top of the section, four strands at the bottom  
 232 of the section and two strands in the outside of the section 51 mm (2 in.) above the bottom row of  
 233 strands, as shown in Fig. 3.

234 **Meshing and Material Models**

235 The mesh of all the models were generated automatically using the default mesh size (102 mm [4  
 236 in.]) per element with a tetrahedra geometry. The material properties used for modeling the  
 237 concrete, UHPC, and steel reinforcement in the sections are summarized in Table 2. The FSB  
 238 section and conventional joint concretes were modeled using a conventional concrete model  
 239 (CC3DNonLinCementitious2) with the described ultimate and compressive tensile stresses. The  
 240 UHPC was also modeled using CC3DNonLinCementitious2, but with an increased compressive  
 241 strength ( $f'_c$ ), tensile strength ( $f_t$ ), modulus of elasticity ( $E$ ) and fracture energy ( $G_F$ ), as shown in  
 242 Table 2. The CC3DNonLinCementitious2 material consists of two constitutive models for fracture  
 243 (tension) and plastic (compression) behaviors combined through a simultaneous algorithm solution  
 244 (J. Cervenka & Papanikolaou, 2008). The crack initiation in the fracture model is computed using  
 245 the Rankine failure criterion, which is described by a pyramid region formed by three stress planes  
 246 in a stress space, or Rankine failure surface. A crack is formed when a maximum principal tensile  
 247 stress (in any of the main three stress directions delimited by the failure surface at any finite  
 248 element) exceeds the tensile strength ( $f_t$ ) of concrete (J. Cervenka & Papanikolaou, 2008). The  
 249 crack opening is then determined by the crack band size and the fracture strain as suggested by  
 250 Hordijk (Hordijk, 1991).

251 **Table 2:** *Summary of concrete and steel material models used*

<b>Material</b>	<b>Base Material Prototype</b>	$f_y$ (MPa)	$f'_c$ (MPa)	$f_t$ (MPa)	$E$ (GPa)	$G_F$ (kN/m)
<b>Beams*</b>	CC3DNonLinCementitious2	--	58.6	3.8	30.0	0.080
<b>Conventional Joint</b>	CC3DNonLinCementitious2	--	27.6	2.2	30.0	0.050
<b>UHPC Joint</b>	CC3DNonLinCementitious2	--	126.2	5.5	42.7	0.125
<b>Steel Reinforcement</b>	CCReinforcement	413.7	--	--	199.9	--

252 Note:  $f_y$  = yielding strength;  $f'_c$  = concrete compressive strength at 28 days;  $f_t$  = concrete tensile  
253 strength at 28 days;  $E$  = modulus of elasticity; \*same material for all beams: Control FSB and  
254 specimens with modified joint geometry; 1 ksi = 6.9 MPa; 1 kip = 4.4 kN; 1 in. = 0.025 m.


255 All the steel rebar in the models were specified as typical Grade 60 reinforcement without steel  
256 hardening. The longitudinal prestressing strands were modeled as inactive strands (without active  
257 prestressing force) as the models were used to assess the transverse behavior of the section and the  
258 joint strength.

259 The interface was modeled as a perfect bond between the UHPC and precast section, which was  
260 assumed because previous testing has shown that UHPC has a good bond to conventional concrete  
261 with proper aggregate exposure finish with at least 6-mm (0.25-in.) amplitude. Hence, the need for  
262 proper surface preparation for bond in joint specimens (Graybeal, 2014a).

### 263 **Transverse Joint Capacity**

264 The transverse joint capacity between two adjacent members was investigated through these  
265 numerical analyses using a similar joint testing protocol conducted by Graybeal (Graybeal, 2010).  
266 The boundary conditions, loading condition, and overall specimen geometry (for 1,422-mm [56-  
267 in.] long specimens) are shown in Fig. 4 (a) and (b). Two beam segments with a short length (1,422  
268 mm and 2,845 mm [56 in. and 112 in.]) were placed side by side with a UHPC joint connecting  
269 them (or CIP deck and joint for the FSB control specimen). The supports were located toward the  
270 outside of the beams running parallel to the joint; note that this is perpendicular to the orientation  
271 of the bearings in a bridge in the field as this test measures the transverse response at bridge mid-  
272 span between two beams. The load was then placed on the center edge of the joint region (aligning  
273 the outer wheel patch border to the joint boundary line) to test both the shear transfer and flexure  
274 capacity of the joint. The load is applied through a load plate the size of an HS-20 wheel patch

275 (508 mm by 254 mm [20 in. by 10 in.]), as shown in Fig. 4 (b) based on the AASHTO LRFD  
276 Bridge Design Specifications (American Association of State Highway and Transportation  
277 Officials) (AASHTO, 2014) oriented in the direction of traffic parallel to the joint. Joints were  
278 tested using these support and load conditions for specimens with 1,422-mm and 2,845-mm (56-  
279 in. and 112-in.) lengths to determine the ultimate strength of the joint, joint ductility through the  
280 load-deflection response (based on deformation after non-linear stage), and failure mechanism  
281 determined by the crack pattern at failure. A sample crack pattern and load-deflection response are  
282 shown in Fig. 4 (c) and (d). The 2,845-mm (112-in.) long specimens appeared to be experiencing  
283 closer to a punching shear failure than a flexure failure of the joint. The 1,422-mm (56-in.) long  
284 specimens were all experiencing a clear flexure failure within the capacity of the available load  
285 frame used in the experimental investigation. A flexure failure was desired for this testing, so the  
286 1,422-mm (56-in.) length was chosen for the construction of the experimental specimens.



287


288 **Fig. 4:** Transverse capacity evaluation: (a) applied load relative to joint and supports, (b) top  
 289 view of wheel patch location, (c) 18F1 top and bottom expected cracking pattern before failure  
 290 (others similar), and (d) 18F1 estimated load-deflection response (others similar). (length units:

291 mm, 1 mm = 0.0394 in)

292 The principal stress that developed in the joints under different load conditions was also  
 293 investigated through the FEA. The maximum principal stress for the four joint shapes in the 305-  
 294 mm (12-in.) deep specimens are shown in Fig. 5. There was a concentrated stress that developed  
 295 at service loading at the bottom of the UHPC joint immediately above the bottom ledge. This  
 296 concentrated stress was due to a perfect bond being assumed between the top of the ledge and the



297 UHPC joint. As a result, the top of the ledge was not specified as an exposed aggregate finish for  
298 the beams constructed for the experimental investigation. Additionally, cracking and concentrated  
299 stresses were observed in the top lip of joint A1, shown in Fig. 5 (b). Joint A2 was developed using  
300 FEA to modify the joint to decrease these stress concentrations in the top lip of the joint. The FEA  
301 results were validated through the experimental investigation.



302  
303 **Fig. 5:** Maximum principal stress at the load point in 305-mm (12-inch) deep specimens from  
304 FEA at (a) service load of 35.6 kN (8 kips) and (b) ultimate load (load dependent on joint type)  
305 with cracking in the plane shown in black (1 MPa = 0.15 ksi)

306

307 **EXPERIMENTAL INVESTIGATION**

308 **Specimen Design and Material Properties**

309 Sixteen (16) prestressed slab-beam sections, 1,422-mm (56-in.) long by 1,524-mm (60-in.) wide,  
310 were built by a local precaster to construct the joint systems using two beams each, shown in Fig.  
311 2. Six of these beams were 457-mm (18-in.) deep (18F1, 18F2, and 18A1 pairs). The other 10 were  
312 precast at 305-mm (12-in.) deep (12F1, 12F2, 12A1, 12A2, and FSB pairs). The FSB section was  
313 precast at 305-mm (12-in.) deep and then a 152-mm (6-in.) deep CIP deck was cast on top with  
314 the joint giving the overall tested section a depth of 457 mm (18 in.). The thicknesses for all the  
315 specimens were summarized in Fig. 3. The reinforcement details for each modified joint beam was  
316 based on the original FSB design (FDOT, 2016b). Two joint tests were conducted for each pair of  
317 precast beams, designated by the last number in the specimen name (e.g., 18F2-1 is the first test  
318 on the 18F2 set of specimens).

319 The precast concrete mix specified for all the beam specimens was FDOT Concrete Class VI with  
320 a minimum compressive strength at 28 days of 58.6 MPa (8,500 psi) and maximum water/cement  
321 ratio of 0.37 kg/kg (lb/lb). The required concrete mix for the CIP deck in the original FSB joint  
322 was FDOT Class II (bridge deck) with a minimum compressive strength at 28 days of 31 MPa  
323 (4,500 psi) and maximum water/cement ratio of 0.44 kg/kg (lb/lb). The UHPC mix used for the  
324 joint connections was specified to be Ductal® JS1000, which is a proprietary UHPC mixture  
325 commonly used for field-cast closure pours for prefabricated bridge element connections. The  
326 UHPC mix ingredients, dosages, and mixing procedure were all provided by the manufacturer.  
327 The specified and assumed concrete compression strength for the precast section and joint material  
328 are shown in Fig. 3.

329 **Table 3:** *Material properties for experimental specimens*

Specimen	Section $f'_c$ (MPa)		Joint $f'_c$ (MPa)		Thickness of section (mm)	Joint Preparation
	Specified	Measured	Specified	Measured		
<b>FSB-1</b>	58.6	85.5	27.6	44.8	457.2*	Sandblasted <sup>1</sup>
<b>FSB-2</b>	58.6	87.6	27.6	9.7	457.2*	Sandblasted <sup>1</sup>
<b>18A1-1</b>	58.6	77.9	144.8	164.1	457.2	Sandblasted <sup>1,2</sup>
<b>18A1-2</b>	58.6	75.8	144.8	160.6	457.2	Sandblasted <sup>1,3</sup>
<b>18F1-1</b>	58.6	82.0	144.8	169.6	457.2	Sandblasted <sup>1,2</sup>
<b>18F1-2</b>	58.6	80.7	144.8	165.5	457.2	Sandblasted <sup>1,3</sup>
<b>18F2-1</b>	58.6	82.0	144.8	175.8	457.2	Sandblasted <sup>1,2</sup>
<b>18F2-2</b>	58.6	84.1	144.8	171.7	457.2	Sandblasted <sup>1,3</sup>
<b>12A1-1</b>	58.6	86.2	144.8	160.0	304.8	Sandblasted <sup>1,2</sup>
<b>12A1-2</b>	58.6	95.1	144.8	178.6	304.8	Sandblasted <sup>1,3</sup>
<b>12F1-1</b>	58.6	85.5	144.8	160.0	304.8	Sandblasted <sup>1,2</sup>
<b>12F1-2</b>	58.6	86.2	144.8	187.5	304.8	Sandblasted <sup>1,3</sup>
<b>12F2-1</b>	58.6	81.4	144.8	164.8	304.8	Sandblasted <sup>1,2</sup>
<b>12F2-2</b>	58.6	86.2	144.8	168.9	304.8	Sandblasted <sup>1,3</sup>
<b>12A2-1</b>	58.6	77.2	144.8	166.9	304.8	Paste Retarder <sup>3,4</sup>
<b>12A2-2</b>	58.6	84.1	144.8	175.8	304.8	Paste Retarder <sup>3,4</sup>

330 Note:  $f'_c$  = concrete compressive strength at 28 days; \*thickness of section includes 152.4 mm

331 CIP deck; <sup>1</sup>sandblasting resulted in an exposed aggregate finish with less than 1.6 mm

332 roughness; <sup>2</sup>joint UHPC was mixed with improper admixtures; <sup>3</sup>joint UHPC was mixed with

333 proper admixtures; <sup>4</sup>Use of paste retarder resulted in an exposed aggregate finish with 3.2 mm

334 roughness; 1 in. = 25.4 mm; 1 ksi = 6.9 MPa.

335

336 The precast beam fabrication, beam delivery to the FDOT Structures Research Center (SRC),  
337 UHPC joint casting, and FSB deck fabrication are shown in Fig. 6. Three sizes of Grade 60 mild  
338 steel reinforcement were used to build all the precast specimens: #10 (#3), #13 (#4), and #16 (#5)  
339 reinforcement. Ten fully bonded, pre-tensioned, 15-mm (0.6-in.) diameter Grade 270 strands were  
340 used in the precast sections with a small amount of prestressing (103.4 MPa [50 ksi]), as shown in  
341 Fig. 3. The strands were needed to support the mild reinforcement in the beam section, but likely  
342 did not play a role in the transverse capacity of the joint strength.




343  
344 **Fig. 6:** Construction of joint specimens: (a) precast specimen concrete pour, (b) delivery of slab-  
345 beam specimens to FDOT SRC, (c) casting of field-cast UHPC, and (d) FSB deck casting.

### 346 Test Setup and Loading Protocol

347 The supports and testing frame used for the experimental program are shown in Fig. 7. The test  
348 setup consisted of two main supports parallel to the joint and holding the specimens in a simply-  
349 supported configuration with a vertical clearance of 1,118 mm (44 in.) from the ground to the

350 bottom of the specimen; this allowed to monitor displacements and cracks underneath the joint for  
 351 ease. Each support was grouted to the strong floor to ensure levelness and avoid undesired  
 352 movement or rotations. The simply-supported specimens were loaded by a hydraulic jack with a  
 353 2,046.2-kN (460 kip) static and fatigue capacity and a variable stroke length of 254 mm (10 in.).  
 354 The load application point was a steel plate with a 508-mm by 254-mm (20-in. by 10-in.) surface  
 355 area and 51-mm (2-in.) thickness with a bottom neoprene bearing pad of the same size. The load  
 356 area is similar to the wheel patch of an AASHTO HS-20 truck (AASHTO, 2014).



357  
 358 **Fig. 7.** Testing frame layout: (a) supports elevation and specimen layout and (b) supports plan  
 359 layout (actuator centerline parallel to longitudinal joint). (units: mm, 1 mm = 0.0394 in)

360 Specimens were tested to determine their ultimate strength and fatigue performance. Strength  
 361 testing consisted of the application of a monotonic load at an approximate rate of 0.9 kN/s (0.2  
 362 kips/s). Loading was typically applied in 44.5-kN (10-kip) increments until 65 percent of the  
 363 expected ultimate capacity. The specimen being tested was inspected for cracks, cracks marked,  
 364 and pictures taken in between each load step until 65 percent was reached. The specimen was then  
 365 gradually loaded until failure.

366 Two joint tests were performed on each pair of beams as both beam sides were built with the  
367 specified joint geometry. After the first test was performed, the connected specimens were cut on  
368 one side of the joint region (if the beams did not break apart during test). Then, the beams were  
369 rotated so that the unaffected joints were aligned, the joint was cast, and a second test performed.  
370 All the specimens were evaluated in the strength test twice, except for 12F1, 12A1, and 12A2.  
371 These three specimens were tested once for strength alone and once for fatigue and strength.  
372 The loading protocol for fatigue testing was designed to assess the fatigue performance of the joint  
373 on a low-volume, 4-lane urban collector bridge over a 100-year service life, to see if this fatigue  
374 loading would lead to cracking, debonding between the UHPC and precast system, or other  
375 degradation of the joint performance. This first stage of fatigue loading consisted of 1.1 million  
376 cycles of load between 8.9 kN and 56.2 kN (2 kip and 12.64 kip) at 2 Hz. The upper limit value  
377 was obtained using a single HS-20-wheel load amplified to include a dynamic load allowance of  
378 33 percent. This dynamic load allowance should have been 15 percent for fatigue limit states, but  
379 the results with the 33 percent dynamic load allowance are conservative.  
380 The second stage of fatigue loading was used to evaluate the effect of cycling from below to above  
381 the cracking load on crack and damage growth, debonding of joint reinforcement, and overall  
382 degradation of the system performance. The fatigue load range was selected based on the static  
383 test results. The lower fatigue load was selected approximately 10 percent less than the cracking  
384 load measured from the static tests. The load range was selected such that the stress range in the  
385 joint reinforcement was 137.9 MPa (20 ksi), a stress range recommended by Helgason et al.  
386 (Helgason, Hanson, Somes, Corley, & Hognestad, 1976) to avoid fatigue of the reinforcement  
387 itself since this was not the purpose of this fatigue testing. The stress range was determined based  
388 on strain measurements in the joint reinforcement during the static testing. Using this stress range,

389 a load range of 84.5 kN to 133.4 kN (19 kip to 30 kip) was selected for these specimens. The  
390 scheduling of the laboratory testing allowed for a total of 2 million cycles for all the fatigue stages  
391 for each specimen, so 900,000 cycles at this post-cracking load range were applied to each of the  
392 three specimens tested in fatigue.

393 The ultimate strength of the specimens after the fatigue loading were then determined through a  
394 static loading protocol similar to that described earlier. This post-fatigue static testing was  
395 performed to see if fatigue testing had any negative influence on the ultimate strength of the joint.


#### 396 **Instrumentation**

397 Four types of sensors were used to measure the response of the joint specimens: unidirectional  
398 concrete surface strain gauges oriented perpendicular to the joint, unidirectional rebar strain gauges  
399 installed on each joint rebar, linear crack opening transducers across the bottom joint between  
400 beams, and laser displacement transducers to measure the vertical deflections at different locations  
401 of the specimen. The laser displacement transducers were placed at three locations along the joint  
402 on the top of the specimen. The hydraulic jack had a built-in load cell capable of measuring the  
403 load being applied to the joint sample.

#### 404 **EXPERIMENTAL RESULTS AND DISCUSSION**

405 A summary of the measured flexural strengths found through the experimental testing is shown in  
406 Fig. 8 alongside the estimated flexural strength from FEA and stress block calculations per  
407 AASHTO § 5.6.3.2.3 (AASHTO, 2014). Results from the first and second test on each joint are  
408 shown with a different shading used to highlight when the second test was performed after fatigue  
409 testing of a joint. The load versus deflection response for all of the experimental specimens are  
410 shown in Fig. 9 (a) for the 457-mm (18-in.) specimens and Fig. 9 (b) for the 305-mm (12-in.)

411 specimens. The load-deflection curve for the FSB specimen is also shown as a comparison point  
 412 for the 457-mm (18-in.) deep UHPC joints.




413


414

**Fig. 8:** Ultimate flexural strength comparison. (1 kN-m = 0.738 k-ft)





(a)



(b)

415

416 **Fig. 9:** Load versus deflection responses with maximum loads for (a) 457-mm (18-inch) deep and

417 (b) 305-mm (12-inch) deep specimens; \*Monolithic response after fatigue testing completed

418 **Performance of Numerical Modeling**

419 There was an overall good agreement between the numerical results and the experimental results

420 other than for the FSB specimens, see Fig. 8. The predicted ultimate flexural strength in the 457-



421 mm (18-in.) specimens was in good agreement with the experimental response (less than 10

422 percent difference): 18F1 with 372 kN-m (3,293 k-in) predicted versus 371.5 kN-m (3,288 k-in)  
423 average from tests, 18F2 with 420.5 kN-m (3,722 k-in) versus 431 kN-m (3,815 k-in) average from  
424 tests, and 18A1 with 337.6 kN-m (2,988 k-in) versus 373 kN-m (3,301 k-in) average from tests.  
425 There was also good agreement of the predicted and tested experimental ultimate flexural strength  
426 for the 305-mm (12-inch) specimens: 12A1 with 122.5 kN-m (1,084 k-in) versus 159.6 kN-m  
427 (1,413 k-in) average from tests, 12F1 with 171 kN-m (1,514 k-in) versus 169.9 kN-m (1,504 k-in)  
428 average from tests, 12F2 with 228.2 kN-m (2,020 k-in) versus 245.1 kN-m (2,169 k-in) average  
429 from tests, and 12A2 with 260.2 kN-m (2,303 k-in) versus 237.6 kN-m (2,103 k-in) average from  
430 tests. There was a significant difference between the estimated and measured response for the FSB  
431 specimens, due to a different failure mechanism occurring in the tested FSB specimens than  
432 predicted by the FEA. The FEA results for the FSB specimens were used as the comparison point  
433 for the developed UHPC joints due to the overall good agreement between the FEA and  
434 experimental results for the other specimens. An estimated strength was also determined using the  
435 rectangular stress block approach for calculating nominal flexural strength; this estimated strength  
436 was less than the measured strength for all test specimens other than the FSB specimens.

#### 437 **Performance of Current FSB Joint Detail**

438 Both FSB control specimen tests failed due to a development failure of the joint reinforcement  
439 before yielding of the joint reinforcement occurred, as shown in Fig. 10 (a). The specimens had  
440 the same slope as the FEA model estimate until a crack developed at the location of one hook,  
441 which was the beginning of the development failure. The specimens then continued to maintain  
442 load as the specimen continued to deflect resulting from the hook pulling out of the joint. The  
443 original FSB design guidelines (FDOT, 2016a) specify #16 (#5) joint reinforcement with a 90-  
444 degree hook and typical 64-mm (2.5-in.) bend diameter, as shown in Fig. 10 (b). The hooked joint

445 reinforcement from adjacent beams is spliced together with hoop bars and straight bars extending  
446 the length of the joint placed between the hook and the hoop. This detail was designed to ensure  
447 proper force transfer between adjacent beams. The actual bend diameter of this joint reinforcement  
448 was larger than specified, as shown in Fig. 10 (c). This larger bend diameter resulted in the joint  
449 reinforcement not being able to develop, which led to a lower transverse flexural capacity than  
450 expected. The larger bend diameter resulted in the constructed hook having lower bearing stresses  
451 in the bend region and less length for stresses on the back of the tail of the hook to prevent the tail  
452 from kicking out; both of these factors would have contributed to the development failure of the  
453 hook. Additionally, the longitudinal reinforcement, placed inside the bend radius of the joint  
454 reinforcement to improve the splice behavior, bent during testing making it less effective at aiding  
455 with the splice connection. Additional joint reinforcement was added to the joint for FSB-2 to  
456 improve the splice behavior, but a much lower concrete strength was received for this joint than  
457 was specified, which further contributed to a lower failure load.



458

459 **Fig. 10:** FSB joint performance: (a) load versus deflection response (b) specified joint detail  
 460 with 64-mm bend diameter for hooks and (c) actual joint reinforcement with larger than 64-mm  
 461 bend diameter for hooks. (length units: mm, 1 mm = 0.0394 in)

462 These test results highlight the importance of having the proper bend diameter, reinforcement  
 463 detail and joint concrete strength for satisfactory performance of the joint. Although the proper  
 464 bend diameter was not achieved in the test specimens for this research, there are no issues reported  
 465 right now in the field with already deployed FSB systems. This may be due to a combination of

466 the properly constructed detail exhibiting satisfactory behavior and the actual joint not  
467 experiencing the same level of load that was tested.

#### 468 **Performance of Developed Joint Details**


469 When looking at the 457-mm (18-in.) deep specimens, the UHPC joints performed similar to or  
470 better than the predicted response for the FSB control specimen. The 18F2 joint had the highest  
471 capacity, with about a 10-percent higher capacity than the FSB control and other joints. This higher  
472 capacity was a result of an increased lever arm of the joint reinforcement, which translated to  
473 enhanced transverse flexural capacity. Though the increased lever arm came at the cost of  
474 constructability, as the 51-mm (2-in.) bottom lip with no reinforcement extending into it can be  
475 easily broken off during fabrication and shipping. The other 457-mm (18-in.) deep specimens  
476 (18F1 and 18A1) had similar capacities to the FSB control specimen as their lever arms only varied  
477 by about 10 mm (0.4 in.). The 18A1 joint had an increased ultimate deflection and deflection at  
478 ultimate load; 18A1 had the largest ultimate deflection and deflection at ultimate load of all the  
479 investigated UHPC joint details due to increased joint rebar embedment length.

480 The 305-mm (12-in.) deep specimens were tested to compare the flexural performance of the joint  
481 in the thinnest standard slab beam section that is standardized by FDOT. Because the current  
482 standard is a 305-mm (12-in.) deep precast section with a 153-mm (6-in.) thick CIP deck, no  
483 control comparison was possible for the 305-mm (12-in.) deep members. The lever arm of the joint  
484 reinforcement had a more pronounced impact on the flexural strength of these members: 12F2 and  
485 12A2 had the largest lever arm for the joint reinforcement and had the highest strength. The  
486 available embedment and splice length impacted the ductility of the section: 12A2 had a larger  
487 splice length and an embedment length equal to or larger than the other joints and had the highest  
488 ductility. Finally, the ultimate strength of the joints was not negatively impacted by the applied

489 fatigue loading. 12A1, 12F1, and 12A2 all had similar ultimate strengths after fatigue loading (test  
490 2) compared to their strengths without fatigue loading first (test 1).

491 There were two primary failure modes observed in the joint specimens:

492 1. **Failure due to lack of embedment or splice length:** Three different types of development  
493 failures were observed in the joint reinforcement, shown in Fig. 11 (a), (b), and (c), due to  
494 a lack of embedment or splice length provided. In FSB-1 a failure occurred when crack  
495 developed at the location of the hook in the joint reinforcement, see Fig. 11 (a). The  
496 reinforcement in 18F1-1, 12F1-2, and 12F2-2 experienced a development failure of the  
497 joint reinforcement when there was some combination of a splitting crack developing at  
498 the location of the reinforcement and a cone developed around the joint reinforcement  
499 along the length of the joint. 12F1-2 had a splitting crack visible on the outside of the joint  
500 at the level of the joint reinforcement, see Fig. 11 (b). For 18F1-1 and 18F2-2, the UHPC  
501 remained bonded to some of the joint reinforcement, but a cone of UHPC around the  
502 reinforcement pulled away with some of the reinforcement from the joint causing a  
503 development failure, see Fig. 11 (c) and (d); this type of development failure typically  
504 occurs when there is sufficient bond between the reinforcement and concrete but  
505 insufficient embedment or splice length. Many of these development failures started with  
506 cracking along the interface between the precast section and UHPC joint.



507

508 **Fig. 11:** Failure mechanism observed during testing: (a) pullout of hooked reinforcement in  
509 *FSB-1* (hooked joint reinforcement shown), (b) pullout of straight joint reinforcement caused by  
510 *splitting crack in 12F1-1* (*splitting crack shown after unloading*), (c) pullout of straight joint  
511 *reinforcement in 18F1-1* (*bottom view shown*), (d) pullout of straight joint reinforcement with  
512 *conical failure in 12F2-2*, and (e) *crushing of concrete in top of section in 12A2-1*.

513

514        2. **Crushing of concrete at top of section:** Crushing of concrete along the top of the joint  
515            and fracture of joint reinforcement was the predominant failure in the specimens with a  
516            diamond shaped joints (18A1, 12A1, and 12A2), similar to Fig. 11 (e). These specimens  
517            had a larger deflection at ultimate load and ultimate deflection, as highlighted in Fig. 9.  
518            Fracture of the joint reinforcement in these specimens was observed in these specimens  
519            when the load was removed, and they were removed from the test frame.

520        There were constructability issues and early cracking observed in the specimens with 51-mm (2-  
521        in.) thick bottom lips (12F2 and 18F2). The precaster commented that it was difficult to cast this  
522        specimen at only a 1,422-mm (56-in.) length and it would be very difficult for them to cast a full-  
523        length beam, as the lip can easily break off when the formwork is being removed. The bottom lip  
524        on one of the specimens (12F2) was damaged during shipping and placement of the beams; a repair  
525        was done on this specimen before casting of the UHPC joint. Additionally, cracking extended  
526        through the bottom lip in all these specimens, as shown in Fig. 11 (c).

#### 527        **Interface Surface Finish and Bond to UHPC**


528        The experimental testing also revealed the importance of surface finish and the workability of  
529        UHPC to achieve sufficient bond between the precast concrete and UHPC in the joint. Past  
530        research has shown that an exposed aggregate finish with a 6.3-mm (0.25-in.) magnitude surface  
531        roughness provides good texture for adequate bond between the precast element and the fresh  
532        UHPC (Graybeal, 2014a). This finish is traditionally achieved by painting a paste retarder on  
533        formwork prior to casting and then using a pressure washer to remove the soft cement paste within  
534        24 hours of casting.

535        Fourteen (14) of the 16 beams were cast at the same time. Heavy sandblasting was used for the  
536        specimens 305-mm and 457-mm (12-in. and 18-in.) deep with F1, F2, and A1 joints, to achieve



537 the specified 6.3-mm (0.25-in.) magnitude exposed aggregate finish that has been recommended  
538 by previous researchers (Graybeal, 2014a). The finish that was achieved for these specimens,  
539 shown in Fig. 12 (a), was less than 1.6 mm (0.0625 in.), not the specified 6.3-mm (0.25-in.)  
540 magnitude finish. Additionally, incorrect admixtures were initially sent with the UHPC that  
541 provided only a short working time and limited flowability of the UHPC for the first tests on these  
542 joint specimens. These two factors led to debonding between the precast section and UHPC joint  
543 in all these tests, as shown in Fig. 12 (b) and (c). The proper admixtures for sufficient working  
544 time and flowability were obtained for casting of the joints for all the second tests, but debonding  
545 still occurred in these tests, which was likely a result of having a smoother joint surface finish than  
546 specified.

547 The recommended procedure for achieving the exposed aggregate finish was used for the last two  
548 specimens that were cast (12A2). A set-retarding admixture was painted on the side forms prior to  
549 casting. The forms were removed one day after casting, and the surface was pressure washed using  
550 constant 24.1 MPa (3,500 psi) water pressure at a controlled distance of application. A 3.2-mm  
551 (0.125-in.) magnitude exposed aggregate finish was achieved using the recommended procedure,  
552 shown in Fig. 12 (d). Although the finish was not the recommended 6.3-mm (0.25-in.) magnitude,  
553 it still offered improved bond compared to the sandblasted finish, as shown in Fig. 12 (e).



554


555 **Fig. 12:** *Impact of joint surface finish on performance: (a) surface finish obtained using heavy*  
556 *sandblasting, (b) debonding during testing of 18A1-1 (occurred in majority of these specimens*  
557 *with sandblasted finish), (c) failure plane of 18A1-1 after specimen removed from test setup, (d)*  
558 *surface finish obtained using paste retarder on forms for 12A2-2, (e) failure of 12A2-2.*

559 Even though the precast joint surface finish did not seem to play a role in the ultimate capacity of  
560 the connection under monotonic load, it is thought to be a critical factor in the long-term service  
561 life of the joint. Insufficient bond may lead to early separation at the interface, which can expose  
562 the protruding steel to early pollution penetration like carbonation and/or chlorides in harsh marine  
563 environments. This can impact the transverse capacity and may lead to the slab beam  
564 superstructure no longer behaving as a solid unit.

### 565 **Fatigue Performance of Joint Specimens**

566 Fatigue testing was conducted on three of the 305-mm (12-in.) deep joint specimens: 12F1-2,  
567 12A1-2, and 12A2-2. The normalized absolute stiffness for all three fatigue specimens is shown

568 in Fig. 13 (a) through (c), respectively. The stiffness was calculated every thousandth cycle by  
569 dividing the difference between the upper and lower applied load by the corresponding difference  
570 between the upper and lower deflection. The normalized stiffness was found by dividing this  
571 calculated stiffness for every thousandth cycle by the stiffness of the first cycle, as described by  
572 Garber (Garber, Gallardo, Deschenes, & Bayrak, 2015). Cracking of these specimens or other  
573 degradation in overall behavior caused by fatigue loading would cause a change in the normalized  
574 stiffness. For 12A1-2 and 12A2-2, the change in normalized stiffness can be seen between the  
575 before and after cracking fatigue phases. 12F1-2 was accidentally cracked prior to fatigue loading  
576 generating two transverse cracks extending from the joint region to the precast section, seen at  
577 both joint end sides (at the level of joint reinforcement); this accidental crack pattern was similar  
578 to the pattern seen on 12A1-2 and 12A2-2 after concluding the after-cracking phase. Although the  
579 accidental load was not measured, the magnitude was larger than the specimen cracking load,  
580 thought to be between 178 and 222 kN (40 and 50 kips). The accidental load is the reason why  
581 there was no change in the normalized stiffness between the before and after cracking fatigue  
582 phases, and there was no further crack growth or decay of behavior during the cycle applications.  
583 Overall, there was no noticeable drop in the stiffness in any of the three joints that would indicate  
584 cracking in the joint during the before-cracking phase or decay in the joint strength capacity during  
585 the after-cracking phase.



586

587 **Fig. 13:** Normalized absolute stiffness every thousandth cycle of system for joints (a) 12F1-2, (b)

588 12A1-2, and (c) 12A2-2. \*Cracked specimen due to accidental load.

589 Also, as previously mentioned, the ultimate strength of each joint was tested following the fatigue

590 testing. The ultimate strengths were comparable for specimens tested with and without prior

591 fatigue testing: the ultimate strength of 12F1-2 decreased by about four percent after fatigue

592 testing, and the ultimate strength of 12A1-2 and 12A2-2 both increased by about 10 percent. These

593 measured ultimate strengths with and without fatigue testing have similar variability to the two  
594 tests conducted without fatigue testing (18A1, 18F1, 18F2, and 12F2), as shown in Fig. 8.

## 595 **CONCLUSIONS**

596 Several conclusions can be made based on the construction and experimental results of the joint  
597 tests:

- 598 • The control FSB joint (FSB-1 and FSB-2) did not perform as expected due to a  
599 larger bend diameter (FSB-1) and due to the compressive strength of the deck  
600 concrete being much lower than specified (FSB-2). These issues caused  
601 development failure of the joint reinforcement prior to yield.
- 602 • All 457-mm (18-in.) deep UHPC joints performed similar to or better than the  
603 predicted response of the FSB section using FEA (assuming no development failure  
604 occurred).
- 605 • Joint 18A1 (with a shear key and increased embedment length of the joint  
606 reinforcement) had the largest deflection at ultimate load and largest ultimate  
607 deflection of the 457-mm (18-in.) deep joints with a comparable ultimate strength.
- 608 • Joint 12A2 (with a shear key and increased embedment and splice length of the  
609 joint reinforcement) was the best performing joint of those tested. Although a 457-  
610 mm (18-in.) version was not tested experimentally, the benefits of this joint over  
611 12A1 (with a shear key and shorter splice length of the joint reinforcement than  
612 12A2) will likely translate well to the 457-mm (18-in.) version.
- 613 • A 51-mm (2-in.) thick bottom lip with no reinforcement extending into it presents  
614 challenges with constructability. A thicker bottom lip with reinforcement is  
615 recommended for similar slab beam members.

- 616           • Using heavy sandblasting on the precast beams with SCC resulted in an exposed  
617           aggregate finish of less than 1.6 mm (0.0625-in.). Using a paste retarding agent on  
618           similar beams provided a 3.2-mm (0.125-in.) magnitude exposed finish, which  
619           resulted in improved bond for the two specimens tested (12A2-1 and 12A2-2).
- 620           • The pre-cracking fatigue loading stage did not cause cracking or show any signs of  
621           deterioration in performance for 12A1-2 and 12A2-2. The after-cracking fatigue  
622           loading stage did not cause degradation of the overall behavior for 12A1-2, 12A2-  
623           2, and 12F1-2. Fatigue loading had little effect on the ultimate strength of joints  
624           12A1-2, 12A2-2 and 12F1-2.

625   Based on the results of this testing, joint 12A2 (with a modified shear key shape and longer non-  
626   contact lap splice) appears to have the best performance and constructability. Future testing is  
627   planned on full-scale beams to determine actual joint demands and behavior, provide a comparison  
628   with the demand on the tested small-scale specimens, and develop complete design  
629   recommendations.

## 630   **NOTATIONS**

631	$d_b$	=	diameter of joint reinforcement
632	$E$	=	modulus of elasticity
633	$f'_c$	=	compressive strength of concrete
634	$f_t$	=	tensile strength of concrete
635	$f_y$	=	yield strength of steel reinforcement
636	$G_F$	=	fracture energy
637	$l_d$	=	required development or embedment length
638	$l_s$	=	required lap splice length

639 **DATA AVAILABILITY STATEMENT**

640 Some or all data, models, or code generated or used during the study are available from the  
641 corresponding author by request.

- 642 • Videos from testing
- 643 • Select data from testing and FEA models

644 **ACKNOWLEDGEMENTS**

645 The research presented in this project was supported by the Florida Department of Transportation  
646 (FDOT). The authors would like to thank FDOT for their financial support and the team of  
647 engineers and staff at the Structures Research Center for their assistance in constructing and testing  
648 the specimens. The opinions, findings and conclusions expressed in this publication are those of  
649 the author(s) and not necessarily those of the Florida Department of Transportation or the U.S.  
650 Department of Transportation.

651 **REFERENCES**

- 652 Aaleti, S., & Sritharan, S. (2014). Design of Ultrahigh-Performance Concrete Waffle Deck for  
653 Accelerated Bridge Construction. *Transportation Research Record: Journal of the*  
654 *Transportation Research Board*, 2406, 12–22. <https://doi.org/10.3141/2406-02>
- 655 American Association of State Highway and Transportation Officials (AASHTO). (2014).  
656 *AASHTO LRFD Bridge Design Specification, Customary U.S. Units, 7th Edition*.  
657 Washington, D. C.
- 658 American Society of Civil Engineers (ASCE). (2017). *2017 Infrastructure Report Card*.
- 659 Bell, C. M., French, C. E., & Shield, C. K. (2006). *Application of precast decks and other*  
660 *elements to bridge structures* (No. MN/RC-2006-37; p. 271). Minneapolis, MN:  
661 University of Minnesota.

- 662 Cervenka, J., & Papanikolaou, V. (2008). Three Dimensional Combined Fracture-Plastic  
663 Material Model for Concrete. *International Journal of Plasticity*, 24, 2192–2220.  
664 <https://doi.org/10.1016/j.ijplas.2008.01.004>
- 665 Cervenka, V., Jendele, L., & Cervenka, J. (2016). *ATENA Program Documentation - Theory* (p.  
666 330). Cervenka Consulting.
- 667 Federal Highway Administration (FHWA). (2015). MnDOT/FHWA Precast Slab System  
668 Workshop Summary Report. Retrieved from  
669 <https://www.fhwa.dot.gov/bridge/prefab/slab.cfm>
- 670 Florida Department of Transportation (FDOT). (2013). *SURVEY: FDOT Superstructure Types*  
671 *for Short and Medium Spans*.
- 672 Florida Department of Transportation (FDOT). (2016a). Developmental Design Standards. *Index*  
673 *No. D20450 Series Florida Slab Beam*. Retrieved from  
674 <http://www.dot.state.fl.us/rddesign/DS/Dev/IDDS/IDDS-D20450.pdf>
- 675 Florida Department of Transportation (FDOT). (2016b). Instructions for Developmental Design  
676 Standards. *Index D20450 Series Florida Slab Beam*. Retrieved from  
677 <http://www.dot.state.fl.us/rddesign/DS/Dev/IDDS/IDDS-D20450.pdf>
- 678 French, C., Shield, C., Klaseus, D., Smith, M., Eriksson, W., Ma, Z., ... Chapman, C. E. (2011).  
679 *Cast-in-Place Concrete Connections for Precast Deck Systems (Web-Only Document*  
680 *173)*. Retrieved from National Academies of Sciences, Engineering, and Medicine  
681 website: <https://doi.org/10.17226/17643>
- 682 Garber, D., Gallardo, J., Deschenes, D., & Bayrak, O. (2015). Experimental Investigation of  
683 Prestress Losses in Full-Scale Bridge Girders. *ACI Structural Journal*, 112(5), 12.



- 684 Goldsberry, B. (2015). *Florida Slab Beam (FSB) - Development and Implementation*. Presented  
685 at the Design Training Expo. Retrieved from  
686 <http://www.dot.state.fl.us/officeofdesign/Training/DesignExpo/2015/presentations/FSBD>  
687 [evelopmentandImplementation-BenGoldsberry.pdf](#)
- 688 Graybeal, B. A. (2006). *Material property characterization of ultra-high performance concrete*  
689 (No. No. FHWA-HRT-06-103). Federal Highway Administration.
- 690 Graybeal, B. A. (2010). *Behavior of Ultra-High Performance Concrete Connections between*  
691 *Precast Bridge Deck Elements*. Presented at the 2010 Concrete Bridge Conference:  
692 Achieving Safe, Smart & Sustainable Bridges.
- 693 Graybeal, B. A. (2014a). *Design and construction of field-cast UHPC Connections* (No. FHWA-  
694 HRT-14-084; p. 36). Federal Highway Administration.
- 695 Graybeal, B. A. (2014b). Ultra-high-performance concrete connections for precast concrete  
696 bridge decks. *PCI Journal*.
- 697 Haber, Z., De la Varga, I., Graybeal, B., Nakashoji, B., & El-Helou, R. (2018). *Properties and*  
698 *Behavior of UHPC-Class Materials* (No. FHWA-HRT-18-036; p. 153). Federal Highway  
699 Administration.
- 700 Halverson, M., French, C., & Shield, C. (2012). *Full-Depth Precast Concrete Bridge Deck*  
701 *System: Phase II* (Final Report No. MN/RC 2012-30; p. 204). Minneapolis, MN:  
702 University of Minnesota.
- 703 Helgason, T., Hanson, J. M., Somes, N. F., Corley, W. G., & Hognestad, E. (1976). Fatigue  
704 Strength of High-Yield Reinforcing Bars. *NCHRP Report*, (164).
- 705 Hordijk, D. (1991). *Local Approach to Fatigue of Concrete* (Dissertation). Technische  
706 Universiteit Delft, The Netherlands.

- 707 Menkulasi, F., Cousins, T., & Wollmann, R. (2018). *Implementation of a Precast Inverted T-*  
708 *Beam System in Virginia: Part II: Analytic and Field Investigation* (Final Report No.  
709 FHWA/VTRC 19-R2; p. 76). Blacksburg, VA: Virginia Polytechnic Institute and State  
710 University.
- 711 Menkulasi, F., Mercer, M., Wollmann, C., & Cousins, T. (2012). Accelerating Bridge  
712 Construction Using the Precast Inverted T-Beam Concept. *Precast/Prestressed Concrete*  
713 *Institute (PCI)*.
- 714 Nolan, S., Freeman, C., Kelley, A., & Rossini, M. (2018, October). *Advancing Small Bridges*  
715 *(Florida Down Under)*. Presented at the 5th International fib Congress, Melbourne, AU.
- 716 Russell, H. G., & Graybeal, B. A. (2013). *Ultra-High Performance Concrete: A State-of-the-Art*  
717 *Report for the Bridge Community* (No. FHWA-HRT-13-060; p. 171). Federal Highway  
718 Administration.
- 719 Smith, M., Eriksson, W., Shield, C., & French, C. (2008). *Monitoring and Analysis of Mn/DOT*  
720 *Precast Composite Slab Span System (PCSSS)* (No. MN/RC 2008-41; p. 219).  
721 Minneapolis, MN: University of Minnesota.
- 722 Texas Department of Transportation (TxDOT). (2018). *Prestressed Concrete Decked Slab Beam*  
723 *Standards* (No. table14e). Retrieved from  
724 <https://www.dot.state.tx.us/insdtdot/orgchart/cmd/cserve/standard/bridge-e.htm>
- 725 Yuan, J., & Graybeal, B. (2014). *Bond Behavior of Reinforcing Steel in Ultra-High Performance*  
726 *Concrete* (Final Report No. FHWA-HRT-14-090; p. 78). McLean, VA: Office of  
727 Infrastructure Research & Development.
- 728 Yuan, J., Graybeal, B., & Zmetra, K. (2018). *Adjacent Box Beam Connections: Performance and*  
729 *Optimization* (No. FHWA-HRT-17-093; p. 129). Federal Highway Administration.

